



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 5

Quadrangle Centerpoint

Permit No. DOD-819

WELL RECORD

Oil or Gas Well Gas
(KIND)

Company National Producers Inc.
Address Box 218 Ferrisboro W.Va.
Farm Davis Acres 50
Location (waters) Long Run 1130'
Well No. 1 Elev. 1110
District Greenbrier County Doddridge
The surface of tract is owned in fee by Jeff Davis
Address Salem
Mineral rights are owned by Jeff Davis Heirs
Address _____
Drilling commenced Aug 20 1962
Drilling completed Sept 19 1962
Date Shot _____ From _____ To _____
With _____
Open Flow /10ths Water in Show Inch
/10ths Merc. in Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
WELL ACIDIZED _____

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16	16'	Steel Conductor	
13			
10	360'	0000	Size of
8 1/4	1236'	1236'	
6 3/4			Depth set
5 3/16			
3 1/4	2262'	2262'	Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED 4" SIZE 2262 No. Ft. 9/19/62 Date

60 sks. cement-10 aquagel-Lawson

COAL WAS ENCOUNTERED AT 755 FEET 2 1/2 INCHES

FEET INCHES FEET INCHES

FEET INCHES FEET INCHES

WELL FRACTURED Dowell Chemical 1000 berell of water, 50,000 lbs. sand


RESULT AFTER TREATMENT 300,000 Thousand

ROCK PRESSURE AFTER TREATMENT 280 lbs - 24 lbs.

Fresh Water _____ Feet Salt Water _____ Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Soil	Brown	Soft	00	15			
Sand	Yellow	Hard	15	35			
Red Rock	Red	Soft	35	45			
Sand	Yellow	Med	45	55			
Slate	White	Med	55	65			
Red Rock	Red	Soft	65	85			
Sand	White	Med	85	160			
Slate	Black	Med	160	215			
Lime	White	Hard	215	265			
Lime	Red	Hard	265	334			
Red Rock	Red	Soft	334	345			
Sand	White	Hard	345	440			
Shells	Black	Med	440	480			
Red Lime	Red	Hard	480	495			
Slate Shells	White	Med	495	510			
Sand	White	Med	510	525			
Red Lime	Hard	Hard	525	585			
Shells	Med	Med	585	714			
Sand	Hard	White	714	755			
Shale Coal	Soft	Black	755	762			
Sand&Slate	White	Med	762	842			
Lime	Black	Hard	842	855			
Shells	White	Med	855	864			
Lime	Grey	Hard	864	900			
Sand	White	Med	900	935			
Pink Rock	Pink	Med	935	966			
Shells&Sand	Grey	Hard	966	1020			
Red Rock	Red	Hard	1020	1037			
Slate	White	Med	1037	1088			
Red Rock	Red	Soft	1088	1119			
Slate	White	Med	1119	1140			

Run 360' 10'



Formation	Color	Hard or Soft	Top 5	Bottom	Oil, Gas or Water	Depth Found	Remarks
Red Rock	Red	Soft	1140	1140 1202			
Lime	Black	Hard	1202	1276			
Shells	White	Med	1276	1290			Run 8" Pipe 1231
Gas Sand	Grey	Hard	1290	1384			
Sand	White	Med	1384	1470			Show of Oil 1440
Shells	Black	Hard	1470	1540			
1st Salt Sand	White	Hard	1540	1580			
Slate	Black	Med	1580	1675			
2nd Salt Sand	White	Hard	1675	1735			
Lime & Shells	Black	Hard	1735	1830			
3rd Salt	Black	Hard	1830	1895			
Lime	Dark	Hard	1895	1900			
Lime	Black	Hard	1900	1925			
Slate	Black	Med	1925	1950			
Maxon Sand	Grey	Med	1950	2005			
Slate	Black	Soft	2005	2020			
Little Lime	Dark	Hard	2020	2055			
Slate	Red	Soft	2055	2085			
Big Lime	Grey	Hard	2085	2164			
Keener Sand	White	Hard	2164	2200			Show of Gas at 2182
Big Injun Sand	Grey	Med	2200	2216			
Lime	Black	Hard	2216	2221			Show of Gas at 2200 to 2214
Squaw Sand	Grey	Med	2221	2230			Show of Gas at 2221 to 2228
Slate	Black	Soft	2230	2262			
			T.D. 2262				

Date _____, 19____

APPROVED _____, Owner

By _____

(Title)