



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION 3

Quadrangle VADIS

Permit No. DOD-1132

WELL RECORD

Oil or Gas Well DRY
(KIND)

Company PENNZOIL COMPANY
Address P. O. Box 1588, Parkersburg, W. Va.
Farm Albert Percy Acres 375
Location (waters) Right Fork of Toms Run
Well No. 15 Elev. 1080.30
District New Milton County Doddridge
The surface of tract is owned in fee by Paul Clevenger
Address Smithville, W. Va.
Mineral rights are owned by Lyle B. Hornor & Co.,
Goff Building Clarksburg, W. Va.
Drilling commenced June 18, 1964
Drilling completed June 28, 1964
Date Shot - From - To -
With -
Open Flow /10ths Water in - Inch
/10ths Merc. in - Inch
Volume - Cu. Ft.
Rock Pressure - lbs. - hrs.
Oil - bbls., 1st 24 hrs.
WELL ACIDIZED -
WELL FRACTURED -


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			-
13			Size of
10			Depth set
<u>8 5/8"</u>	<u>497'</u>	<u>497'</u>	Perf. top
6 3/4			Perf. bottom
5 3/16			Perf. top
3			Perf. bottom
2			
Liners Used			

CASING CEMENTED 8 5/8" SIZE 497 No. Ft. 6/19/64 Date

COAL WAS ENCOUNTERED AT - FEET - INCHES
- FEET - INCHES - FEET - INCHES
- FEET - INCHES - FEET - INCHES

RESULT AFTER TREATMENT -
ROCK PRESSURE AFTER TREATMENT -
Fresh Water - Feet Salt Water - Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Red Shale & Sandy Blue Shale			0	66			
Sandy Shale			66	150			
Sand			150	165			
R. Rock & Shale			165	250			
Sand			250	300			
Sandy Shale			300	312			
Sand			312	329			
Sandy Shale			329	345			
Shale			345	370			
Shale & Sand			370	490			
Sand			490	580			
Sandy Shale			580	650			
Sandy Lime			650	665			
Shale & R. Rock			665	905			
Shale			905	1090			
Sand			1090	1136			
Sand & Shale			1136	1315			
Shale			1315	1335			
Sandy Shale			1335	1420			
Sandy Lime & Shale			1420	1469			
Sand			1469	1565			
Shale			1565	1729			
Sand			1729	1785			
Sandy Shale			1785	1811			
Sand & Lime			1811	1858			
Sandy Shale			1858	1920			
Sand & Shale			1920	1949			
Shale			1949	1951			
Lime & Shale			1951	1986			
Sand			1986	2020			
Lime, Big			2020	2076			



Formation	Color	Hard or Soft	Top 3	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand, Big injun			2076	2157			
Shale			2157	2188			
Pay Section			2152	2154			
TOTAL DEPTH				2188			
This well abandoned June 28, 1964.							

Date July 1, 1964

APPROVED PENNZOIL COMPANY, Owner

By George W. Wilsman
 George W. Wilsman, Manager
 Land-Lease Records Department