





STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION //

Rotary   
Spudder   
Cable Tools   
Storage

Quadrangle Centerpoint

Permit No. DOD-1406

**WELL RECORD**

Oil or Gas Well Both  
(KIND)

Company Prior Oil Company  
Address 224 Washington Blvd., Belpre, Ohio  
Farm J. A. Wilcox Acres 40.5  
Location (waters) \_\_\_\_\_  
Well No. 4 Elev. \_\_\_\_\_  
District Grant County Doddridge  
The surface of tract is owned in fee by J. A. Wilcox  
Address \_\_\_\_\_  
Mineral rights are owned by J. A. Wilcox  
Address \_\_\_\_\_

Drilling commenced September 5, 1966  
Drilling completed October 15, 1966  
Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
With \_\_\_\_\_

Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
\_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch

Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.

Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
WELL ACIDIZED 250 gallon 15% acid

WELL FRACTURED 900 barrels water, 20,000 lb. sand (20-40)

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
<del>XX</del> 17"	30 ft.	30 ft.	Kind of Packer _____
13			
10 3/4	301		Size of _____
8 5/8	1330		
<del>XX</del> 7"	1725		Depth set _____
5 3/16			
<del>X</del> 4 1/2"		2329	Perf. top <u>2251</u>
2			Perf. bottom <u>2255</u>
Liners Used _____			Perf. top _____
			Perf. bottom _____

CASING CEMENTED 4 1/2 SIZE 2339 No. Ft. 10/12/66 Date


COAL WAS ENCOUNTERED AT NONE FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES

RESULT AFTER TREATMENT 15 barrels

ROCK PRESSURE AFTER TREATMENT 500 lb.

Fresh Water \_\_\_\_\_ Feet Salt Water \_\_\_\_\_ Feet

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth	Remarks
Soil			0	12			
Hard Sand			12	49			
Red Rock			49	75			
White Slate			75	90			
Red Rock			90	134			
Sand			134	158			
Red Rock			158	215			
Sand			215	235			
Slate			235	299			
Sand			299	310			
Red Rock			310	322			
Lime			322	340			
R. Rock-Lime			340	545			
Sand			545	571			
R. Rock-Lime			571	625			
White Slate Lime			625	890			
Black Slate			890	1016			
Red Rock			1016	1076			
Sand			1076	1090			
Red Rock			1090	1186			
Sand			1186	1210			
Slate-Shells			1210	1436			
Sand			1436	1460			
Slate			1460	1650			
Sand			1650	1750			
Slate			1750	1802			
Sand			1802	1825			
Slate			1825	2075			



Formation	Color	Hard or Soft	Top //	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand			2075	2117			
Slate			2117	2171			
Big Lime			2171	2248			
Sand <i>INTON</i>			2248	2327	Show Oil		
Shale			2327	2339			

Date \_\_\_\_\_, 19\_\_

APPROVED \_\_\_\_\_, Owner

By \_\_\_\_\_ (Title)