

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

190

WELL RECORD

Oil

Permit No. 736A


Oil or Gas Well (Kind)

Company Hope Construction & Refining Company
 Address Clarksburg, W. Va.
 Farm S. W. Stout Acres 1427
 Location (waters) South Fork Hughes River
 Well No. 1331 Elev. 1291
 District Southwest County Doddridge
 The surface of tract is owned in fee by S. W. Stout
 Address Parkersburg, W.Va.
 Mineral rights are owned by _____
 Address _____
 Drilling commenced 6-7-1900
 Drilling completed 7-31-1900
 Date shot 5-21-1930 Depth of shot 2801-2811
 Open Flow /10ths Water in _____ Inch
 /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water None recorded feet _____ feet
 Salt water 1590 feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	710	Pulled	Size of
8 1/4	1350	Pulled	
6 5/8	1670	1670	Depth set
5 8/10	2255	2255	
3			Perf. top
2	2809	2809	Perf. bottom
Liners Used 4"	596	596	Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____
 Not cemented _____
 COAL WAS ENCOUNTERED AT No coal FEET _____ INCHES _____
 FEET _____ INCHES _____ FEET _____ INCHES _____
 FEET _____ INCHES _____ FEET _____ INCHES _____

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Red Rock Cave		Top	700	700			
Cow Run Sand			1200	1230			
Salt Sand			1570	1670	Water	1590	
Maxon Sand			1935	1965			
Big Lime			2110	2165			
Big Injun Sand			2165	2240	Oil	2170	
Gordon Stray Sand			2790	2805			
Gordon Sand			2808	2812	Oil	2801-2811	
		Total Depth	2833				



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date September 8, 19 38

APPROVED Hope Construction & Refining Co., Owner

By *[Signature]* Asst. General Supt.
 (Title) M

Southwest District, Doddridge County, W. Va.
 By Hope Construction & Refining Co., Clarksburg, W. Va.
 On 1427 acres, on South Fork of Hughes River.
 Elevation, 1291' L.
 Surface owned by S. W. Stout, Parkersburg, W. Va.
 Drilling commenced 6-7-1900; completed, 7-31-1900.
 Shot 5-21-1900, at 2801-2811'.
 No fresh water recorded. Salt water at 1590'.
 10" casing, 710' (pulled); 8", 1350' (pulled); 6", 1670';
 5", 2255'; 4" liner, 596'; 2" tubing, 2809'.
 Casing not cemented. No coal was encountered.
 Oil well. Abandonment reported to Dept. of Mines Sept. 8, 1938.
 Record to RCT from Mrs. Griffith Sept. 22, 1938.

	Top.	Bottom.
Red rock cave	700	- ...
Cow Run Sand	1200	- 1230
Salt Sand (water, 1590')	1570	- 1670
Marion Sand	1935	- 1965
Big Line	2110	- 2165
Big Injun Sand (oil, 2170')	2165	- 2240
Gordon Stray Sand	2790	- 2805
Gordon Sand (oil, 2801-2811')	2808	- 2812
Total depth		2833