


LATITUDE

39° 12' 30"

80° 45'



LONGITUDE

7'5 OGIS topo location

7.5' loc 0.76 S 15' loc _____
 ' 0.49 W (calc.) _____

Company _____

Farm _____

Quad Oxford _____

County _____

District Southwest _____

WELL LOCATION MAP

File No. 017-30240

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

187

WELL RECORD

240-A
AB Permit No. ~~238-A~~ ?


Oil or Gas Well Oil
(Kind)

Company Hope Construction & Refining Company
Address Clarksburg, W. Va.,
Farm D. P. Stout Acres 417
Location (waters) South Fork Hughes River
Well No. 1317 Elev. 1078
District Southwest County Doddridge
The surface of tract is owned in fee by L. M. Stout
Address Blandville, W. Va.
Mineral rights are owned by _____
Address _____
Drilling commenced 1-5-1915
Drilling completed 2-16-1915
Date shot 2-12-1927 Depth of shot Gordon
Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil _____ bbls., 1st 24 hrs.
Fresh water None recorded feet _____ feet
Salt water 1242 feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	460	Pulled	Size of
8 1/4	1070	Pulled	
6 5/8	1752	1752	Depth set
5 3/16	252	252	
3			Perf. top
2	2499	2499	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. FT. _____ Date _____
Not cemented _____
COAL WAS ENCOUNTERED AT 930 FEET 36 INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Sand			536	581	Show Gas	540	
Pittsburgh Coal			930	933			
First Cow Run Sand			1046	1081			
Second Cow Run Sand			1230	1280	Water	1242	
Salt Sand			1385	1429	Show Gas	1497	
Maxon Sand			1482	1510			
Little Lime			1657	1685			
Pencil Cave			1685	1692			
Big Lime			1692	1720			
Keener Sand			1735	1827			
Big Injun Sand			1827	1835			
Squaw Sand			1920	1950			
Gordon Stray Sand			2470	2482			
Gordon Sand			2485	2490	Oil	2488	
Total Depth			2509				



Will

Southwest District, Doddridge County, W. Va.
 By Hope Construction & Refining Co., Clarksburg, W. Va.
 On 417 acres, on South Fork of Hughes River.
 Elevation, 1078' L.

Surface owned by L. M. Stout, Blandville, W. Va.
 Drilling commenced 1-5-1915; completed, 2-16-1915.
 Shot 2-12-1927, in Gordon Sand.

No fresh water recorded. Salt water at 1242'.
 10" casing, 460' (pulled); 8 1/2", 1070' (pulled); 6", 1752';
 5", 252'; 2" tubing, 2699'.

Casing not cemented.

Coal was encountered at 930-933'.

Oil well. Abandonment reported to Dept. of Mines Sept. 14, 1936.
 Record to WGT from Mrs. Griffith Sept. 22, 1936.

	Top.	Bottom.
Sand (show gas, 540')	536	- 581
Pittsburgh? Coal	930	- 933
First Cow Run Sand	1046	- 1083
Second Cow Run Sand (water, 1242')	1270	- 1280
Salt Sand (show gas, 1497')	1385	- 1429
Horton Sand	1482	- 1510
Little Line	1657	- 1685
Pencil Cove	1685	- 1692
Big Line	1692	- 1720
Keener Sand	1735	- 1827
Big In Jan Sand	1827	- 1835
Squaw Sand	1920	- 1950
Gordon Stray Sand	2470	- 2482
Gordon Sand (oil, 2488')	2485	- 2490
Total depth		2509