

Latitude 39° 15' 00"

11 00 00 00 00 00

Longitude

+ 75'

0.902
1.912

Topo Location

7.5' Loc. _____ 15' Loc. _____
_____ (calc.) _____

Company _____

Farm Ralph Legget

15' Quad _____
(sec.)

7.5' Quad Oxford

District Central

WELL LOCATION PLAT

County 017 Permit 30947

RALPH LOGGETT NO. 1 WELL.

947A

Central District, Doddridge County, W. Va.

By P. Douglass Ferr. Adm. of W. D. Gribble Estate, West Union, W. Va.

Abandoned under permit Dad-.....-A?

On 170 acres, on Cabin Run.

Elevation, 815' L.

Surface owned by Ralph Loggett, Rt. 1, West Union, W. Va., and minerals
by C. H. Miller Heirs, William Dotson, Rt. 1, West Union, W. Va.

Drilling commenced Jan. 16, 1917; completed May 4, 1917.

Shot May 8, 1917, with 22 qts.

10" casing, 143'; 8", 1046'; 6", 1901'.

Gas well. Record to Dept. of Mines stamped Oct. 6, 1952.

Record to DOT from Mrs. Griffith Dec. 10, 1952. O.P.No. 884.

	Top.	Bottom.
Pittsburgh Coal	552	557
Little Lunkard Sand	815	845
Big Lunkard Sand	1035	1060
1st Salt Sand	1306	1360
2nd Salt Sand (oil, 1392-96'; cased off)		
(NOTE: We desire to test this oil pay when we plug up to it).	1384	1454
Morton Sand	1730	1750
Big Injun Sand (gas, 1912')	1912	1987
Squaw Sand	1944	1954
Total depth		1963



884

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. 947-A
P. Douglass Farr Administrator of


Oil or Gas Well Gas
(KIND)

Company W. D. Gribble Estate
Address West Union, W. Va.
Farm Ralph Leggett Acres 170
Location (waters) Cabin Run
Well No. 1 Elev. 815
District Central County Doddridge
The surface of tract is owned in fee by Ralph Leggett
Rt. # 1 Address West Union, W. Va.
Mineral rights are owned by C. N. Miller Hrs
c/o Hattie Dotson Rt. #22 1 West Union, W. Va.
Address Jan. 16, 1917
Drilling commenced May 4, 1917
Drilling completed 5-8-17 From To
With 22 Qts
Open Flow /10ths Water in Inch
 /10ths Merc. in Inch
Volume Cu. Ft.
Rock Pressure lbs. hrs.
Oil bbls., 1st 24 hrs.
Fresh water feet feet
Salt water feet feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	143	143	Size of
8 1/2	1046	1046	
6 5/8	1901	1901	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED SIZE No. Ft. Dat
COAL WAS ENCOUNTERED AT FEET INCHES
 FEET INCHES FEET INCHES
 FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pitt Coal			652	657			
L. Dunkard			815	845			
B Dunkard			1035	1060			
1 Salt Sand			1308	1360			
2 " "			1384	1454	Oil	1392-96	Cased off
Maxson			1730	1750			(NOTE We desire to test this oil pay when we plug up to it)
Big Injun			1912	1920	Gas	1912	
Squaw			1944	1954			
Total Depth				1963			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date _____, 19____

APPROVED P. Douglas Fan, Owner
ADMINISTRATOR OF

By W. D. GRIBBLE ESTATE
(Title)

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, ONE COPY MAILED TO THE SUPERVISOR ONE COPY TO BE RETURNED BY THE WELL OPERATOR AND THE THIRD COPY (AND EXTRA COPIES OF RECORDS) SHOULD BE MAILED TO EACH COAL OPERATOR AT THEIR RESPECTIVE ADDRESSES.

Ralph Loggess well operator on owner
W. D. Gribble well operator
W. D. Gribble well operator
 No. 1 West Union, Va.
 West Union, Va. Va.
 November 14, 1932
 WELL AND LOCATION
 Central District
 Doddridge County

NAME ON PROPERTY OWNER: W. D. Gribble Well No. 1
 ADDRESS: Doddridge County
C. H. Miller Farm

STATE INSPECTOR SUPERVISING PLUGGING: HARRY V. MAZE
 AFFIDAVIT

STATE OF WEST VIRGINIA }
 County of Doddridge }
C. C. McConnell and C. H. Miller being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by W. D. Gribble well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 14th day of October, 1932, and that the well was plugged and filled in the following manner:

NAME ON STATE RECORDS	QUANTITY	FILLING MATERIAL		PLUGS USED	CASINGS	
		NO.	SIZE		NO. & SIZE	NO. & SIZE
Red Clay		1963	1931			
Best Cement		1921	1921	5' Crushed Stone		
Red Clay		1921	1446	6-5/8" casing 1880	20	
Best Cement		1446	1436	5' Crushed Stone		
Red Clay		1350	1340	5' Crushed Stone		
Best Cement		1076	1076	5' Crushed Stone		
Best Cement		1066	795	8-1/4" casing 724	20	
Best Cement		795	885	5' Crushed Stone		
Red Clay		785	587	58 Crushed Stone		
Best Cement		587	532	10" casing 124	19	
Red Clay		527	172	5' Crushed Stone		
Best Cement		172	163			
Clay seal casing		158	0			

NOV 1932
 1932

REMARKS OF SUPERVISOR
 Erected marker such as 19 1/2 in Bolt 18, 1931 Regulations

and that the work of plugging and filling said well was completed on the 13th day of November, 1932.
 And further deposes and says that
C. H. Miller
Dr. MICK SMITH

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 INSPECTOR'S PLUGGING REPORT

W. D. Gribble - R. D. Gribble
 C. H. Miller - Ralph Loggess
 Doddridge County, West Virginia

Location	Plugs used and depth plugged	Casings	Remarks
	WOOD CASE	WOOD CASE	1880' 6-5/8" 20'
			724' 8-1/4" 20'
			124' 10" 19'

22/28/32
 1932