


52

Oil-51A



ENGINEERS CERTIFICATE

I, THE UNDERSIGNED HEREBY
 CORRECT AND SHOWS ALL THE
 KNOWLEDGE AND BELIEF REQUIRED
 THE MINING LAWS OF WEST VIRGINIA.

CERTIFY THAT THIS MAP IS
 INFORMATION TO THE BEST OF MY
 BY THE OIL & GAS SECTION OF
John Moore C.E. & M.

ACKNOWLEDGED BEFORE ME THE UNDERSIGNED AUTHORITY BY JOHN D. MOORE,
 THIS THE 8TH DAY OF NOVEMBER 1933.
 MY COMMISSION EXPIRES ON THE 8th DAY OF November 19 33
 IN AND FOR KANAWHA COUNTY.

NOT LOCATED

R. E. & J. L. ALLTOP NO. 1 WELL ~~52-A~~ No. 95 O.F.-Gilmer

Center District, Gilmer County, W. Va. ~~52-A~~
West Virginia Production Co., Charleston, W. Va. (Charles F. Howard).
On 100 acres, owned in fee by R. E. and J. L. Alltop, Clarksburg, W. Va.
Drilled in 1923.
Elevation, 1070' B.
6-5/8" casing, 1505'; 2" tubing, 1850'.
Abandonment reported to Dept. of Mines March 24, 1934.
Well was not shot.
Gas well.

	Top.	Bottom.
Salt Sand	1530	1635
Maxton Sand (gas), to bottom	1780	1850

Name	Color	Character	Oil, Gas or Water	Top	Bottom	Thickness	Total Depth	Remarks
Salt Sand				150	1625			
Maron				1780	1850			
Total Depth						1850		

Well 52-A

3/24/54

Well was not shot at _____ feet; well was shot at _____ feet.

Salt Fresh water at _____ feet; salt fresh water at _____ feet.

Well was producing for _____ hole.

WEST VIRGINIA PRODUCTION COMPANY

March 24, 1954

Approved *Paul F. Howard*

WEST VIRGINIA DEPARTMENT OF MINES

OIL AND GAS DIVISION

PRELIMINARY DATA SHEET NO. 1

File No.

W.V. 52-A

Well No. 1

WEST VIRGINIA

COMMISSION

Company, of

CLARKSBURG, W. VA.

on the

A. L. & J. L. ALLTOP

Part

containing 100 acres. Location

Center

District, in WILSON

County, West Virginia

The surface of the above tract is owned in fee by A. L. & J. L. Alltop

of Clarksburg W. Va.

address, and the mineral rights are owned by

of

The oil and gas privileges are held under lease by the above named company, and this well is drilled under permit

No. issued by the West Virginia Department of Mines, Oil and Gas Division

Drilled 1923

193

Elevation of surface at top of well, 1070

Spring Barometric

The number of feet of the different sized casings used in the well.

feet size Wood conductor

1505 feet 6 5/8" size, csg. feet sized csg.

1850 feet 2" size, csg. tubing feet sized csg.

feet size, csg. feet sized csg.

packer of size, set at

packer of size, set at

, in casing perforated at feet to feet.

, in casing perforated at feet to feet.

Coal was encountered at feet; thickness inches, and at

feet; thickness inches; and at feet; thickness inches.

Linens were used as follows: (Give details)

March 24, 1924

Date

Approved

W. L. Howard

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION
WORK ORDER

Well to be plugged and filled as follows:

Pull 2" tubing

Fill from bottom to 1720-10' above Maxon. Place plug 1780-1777 and cement to 1767. Place permanent bridge at 1525 and fill 1510. ^{Pull 6 5/8" casing} Place plug 1510-1507 and cement to 1497. Remove Casing. Fill to surface and erect a marker in accordance with Rules and Regulations of Dept of Mines, all to be done in workmanlike manner.

To the Department of Mines,
Coal Owner or Operator,
Lease or Property Owner

Gentlemen:

This "work order" is submitted for your approval and concurrence and unless notified of your disapproval or non-concurrence, the undersigned will proceed with the plugging and filling of said well in the above described manner on the date stated in the notice of intention to plug and abandon the said well on opposite side of this sheet.

Very truly yours, W. VA. PRODUCTION COMPANY

BY *Charles J. Arnold*
Well Operator

No objections have been filed by the coal owner or coal operator, or any available adjacent lease or property owners or interposed by the Department of Mines to the manner herein described for the plugging and filling of the well above mentioned. Therefore, the same is hereby approved this 27th day

of March, 198 4

DEPARTMENT OF MINES
Oil and Gas Division

52-A

NOTICE OF INTENTION TO PLUG AND ABANDON WELL

(REQUIRED BY SECTION 9, ARTICLE 4, CHAPTER 22 OF THE CODE)

WEST VIRGINIA DEPARTMENT OF MINES
OIL AND GAS DIVISION

TO THE DEPARTMENT OF MINES
Charleston, W. Va.

No Coal

COAL OPERATOR OR COAL OWNER

ADDRESS

COAL OPERATOR OR COAL OWNER

ADDRESS

R. E. Alltop 721 Baltimore St
Clarksburg, W. Va.

LEGAL PROPERTY OWNER

J. L. Alltop 721 Baltimore St.
Clarksburg, W. Va.

ADDRESS

W. Va. Production Company

NAME OF WELL OPERATOR

509 Kanawha Banking & Trust Bldg.,

Charleston, W. Va.

COMPLETE ADDRESS

March 24, 19 24

WELL TO BE ABANDONED

Center District

Gilmer County

Well No. 1

R. E. & J. L. Alltop Farm

Gentlemen:—

The undersigned well operator is about to abandon the above described well and will commence the

work of plugging and abandoning said well on the 28 day of March, 19 24
(which date shall not be less than five days after the day on which this notice so mailed is received, or in
due course should be received by the Department of Mines).

This notice is given you in order that your respective representatives may be present at the plugging
and filling of said well. You are further notified that whether you are represented or not represented the
undersigned will proceed on that date, or shortly thereafter, to plug and fill said well in the manner
required by Section 10, Article 4, Chapter 22 of the Code and given in detail on the reverse side of this
notice, in "Work Order."

This notice is being mailed by registered mail to each of you at the above addresses on the above date.

Very truly yours,

WEST VIRGINIA PRODUCTION COMPANY

Charles F. Howard
Well Operator

NOTE: Upon the abandonment of all wells drilled prior to June 1, 1925, a plat prepared by a competent en-
gineer, showing the district and county in which the tract of land is located, the name and acreage of same, the
names of the owners of adjacent tracts, and the location of the about to be abandoned well, determined by survey
and the courses and distances of such well from two permanent points or landmarks on said tract, shall be submitted
with this notice.

(Over)