

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: ROGERS Operator Well No.: D R ROGERS 3

LOCATION: Elevation: 1,171.26' Quadrangle: WALLACE WV
District: EAGLE County: HARRISON
Latitude: 39.40875 Feet South of 39 Deg. 24 Min. 31.4961 Sec.
Longitude: -80.40033 Feet West of -80 Deg. 24 Min. 01.2120 Sec.

Well Type: OIL _____ GAS X

Company West Virginia Land Resources, Inc Coal Operator West Virginia Land Resources, Inc
1 Bridge Street or Owner 1 Bridge Street
Monongah, WV 26554 Monongah, WV 26554
Agent David Roddy Coal Operator _____
Permit Issued Date 11/18/2024 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Harrison ss:

Matthew Yearsley and Thomas Thrasher being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of November, 2024, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable with Gas Blocker	2700'	1476'	3 1/2" Casing - 3200'	259'
Expandable	1476'	Surface	7" Conductor - 0'	1476'

Description of monument: 77" of 7" casing with Company Name, Well #, API #, and Date Completed and that the work of plugging and filling said well was completed on the 10th day of December, 2024.

And further deponents saith not. Matthew A Yearsley
Thomas Thrasher



Sworn and subscribe before me this 13th day of January, 2025
My commission expires: August 13th 2029 Kerri A McCormick
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Kenny Willett Title: Inspector **02/07/2025**

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WEST VIRGINIA LAND RESOURCES, INC.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
HARRISON COUNTY COAL
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

WEST VIRGINIA LAND RESOURCES, INC.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE WV
Well Location
EAGLE
District
HARRISON
County
D R ROGERS 3
Well No.
ROGERS
Farm

STATE INSPECTOR SUPERVISING PLUGGING Kenny Willett

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of HARRISON ss:

MATTHEW A. YEARSLEY and THOMAS THRASHER being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by West Virginia Land Resources, INC., operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of November, 2024 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cut 3 1/2" casing at 3300'. A diligent effort was made to pull 3300' of 3 1/2" casing by pulling 150% of the string weight. All attempts were unsuccessful. Cut 3 1/2" casing at 3200' and pulled 3200' of 3 1/2" casing from surface to 3200'. Left 259' of 3 1/2" casing in the hole from 3200' to 3459'. Cleaned 2 3/8" hole from surface to 2700'. Attempted to drill deeper but all attempts were unsuccessful. Cut 7" casing at 730'. A diligent effort was made to pull 730' of 7" casing by pulling 150% of the string weight. All attempts were unsuccessful. Left 1476' of 7" casing in the hole from surface to 1476'.	3 1/2" Casing 7" Casing	3200' 0'	259 1476'
	Cemented hole from 2700' to surface as follows: Cemented hole from 2700' to 1476' using 215 sacks of Expandable Cement with Gas Blocker additive. Cemented hole from 1476' to surface using 230 sacks of Expandable Cement. Cement did circulate at the surface. A total of 445 sacks of cement were used to fill the hole from 2700' to surface.			
Coal Seams		Description of Monument		
Pittsburgh	N/A	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 10th day of December, 2024

And further deponents saith not.



Matthew A Yearsley

Matthew A. Yearsley

Thomas Thrasher

Thomas Thrasher

Sworn to and subscribed before me this 13th day of January

Kerri McCormick
Notary Public

My commission expires: Aug 13th 2029

Permit No. 47-033-00185
Well No. D R ROGERS 3
Latitude: 39° 24' 31.50"N
Longitude: -80° 24' 01.21"W

02/07/2025

Kenny Willett 1/14/25