

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: E.L. Coffman Operator Well No.: 7841

LOCATION: Elevation: 1265.81 Quadrangle: Wallace, WV 7.5'
District: Eagle County: Harrison
Latitude: _____ Feet South of 39 Deg. 24 Min. 25.9 Sec.
Longitude: _____ Feet West of 80 Deg. 22 Min. 44.2 Sec.

Well Type: OIL _____ GAS X

Company Consolidation Coal Co Coal Operator 1 Bridge St
or Owner Monongah, WV 26554

Agent David Roddy Coal Operator _____
Permit Issued Date 6/28/18 or Owner _____

RECEIVED
Office of Oil and Gas

NOV 2 2018

WV Department of
Environmental Protection
Office of Oil and Gas

NOV 2 2018

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Monongalia ss:

Todd E. Brandon and Matthew A. Yearsley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of September, 2018, and the well was plugged and filled in the following manner:

WV Department of
Environmental Protection

TYPE	FROM	TO	PIPE REMOVED	LEFT
Thixotropic	1176'	888'		
Expandable	888'	Surface		
4 1/2"	Unknown	2270'	2270'	0'
7"	1548'	Surface	0'	1548'
10 3/4"	282'	Surface	0'	282'
16"	20'	Surface	0'	20'
2 3/8" DP	2905'	1776'	0'	1138'


Description of monument: 77' of 7' casing with company name, well #, API #, and date cemented. and that the work of plugging and filling said well was completed on the 5th day of October, 2018.

And further deponents saith not.

Sworn and subscribe before me this 5th day of November, 2018

My commission expires: 06/17/2021

Notary Public



Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: O&G Inspector

COPY

FORM WR-38
(Affidavit of Plugging)

WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
MOUNTAINEER COAL COMPANY
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
WALLACE, WV 7.5'
Well Location
EAGLE
District
HARRISON
County
7841
Well No.
E.L. COFFMAN
Farm

RECEIVED
Office of Oil and Gas

NOV 27 2018

WV Department of
Environmental Protection

STATE INSPECTOR SUPERVISING PLUGGING

[Signature]

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

JOSEPH F. THORNE and MATTHEW A. YEARSLEY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6th day of September, 2018 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned a 3 3/4" hole inside 4 1/2" casing from surface to 3564'. Perforated 4 1/2" casing with 4 shots per shot at 2780', 2680', 2580', 2480' and 2380'. Log showed perforations at 3457' and 3444'. Removed 2270' of 4 1/2" casing from surface to 2270'. Left unknown amount of 4 1/2" casing in well from 2270' to unknown depth, due to extreme bond. Left 1138' of 2 3/8" drill pipe in well from 1767' to 2905'. As a result of downhole complications, 2 3/8" drill pipe was un-retrievable. Left 9.2 PPG gel plug from 3564' to 1767'. Left 1548' of 7" casing in well from surface to 1548'. Attempts to remove 7" casing by pulling 150% string weight were unsuccessful. Perforated 7" casing with 4 shots per shot at 900', 800', 700', 602', 496', 400', 300', 200' and 98'. Approximate 282' of 10 3/4" casing in well from surface to 282'.	4 1/2"	2270'	Unknown	
			0'	1548'
		10 3/4"	0'	282'
		16"	0'	20'
		2 3/8" Drill Pipe	0'	1138'
<u>Cemented hole from 1767' back to the surface as follows:</u> From 1767' to surface with 425 sacks of Class A cement. Cement did circulate at surface.				
Coal Seams		Description of Monument		
Pittsburgh		77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 5th day of October, 2018

And further deponents saith not.


[Signature]
Joseph F. Thorne
[Signature]
Matthew A. Yearsley

Sworn to and subscribed before me this 5th day of November, 2018

[Signature]
Notary Public

My commission expires:

06/17/2021



Permit No. 47-033-01133
Well No. 7841
Latitude: 39° 24' 25.9"N
Longitude: 80° 22' 44.2"W