

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: MARCH 16th, 2016
API #: 47-033-01527P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: HURST, E. Operator Well No.: 7047 DEPI (Hope 7968) Plugging (2014)

LOCATION: Elevation: 1327.70' Quadrangle: Wolf Summit
District: Coal County: Harrison

Latitude: 000 Feet South of: 39 Deg. 17 Min. 58 Sec.
Longitude: 000 Feet West of: 80 Deg. 26 Min. 07 Sec.

Well Type: OIL GAS X

Company: CNX Gas Company LLC Coal Operator or Owner See List on Page 2
P.O. Box 1248
Jane Lew, WV 26378

Agent: Matt Imrich
Permit Issued Date: 11/21/2014

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Lewis ss:

Richard C. Jones and Anthony Kendziora being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 12th day of December, 2014, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Class A Cement Plug	2234'	2080'		
6% Gel Plug	2080'	2042'		
5 3/16" csg	2206'	2042'	2042'	164'
6 5/8" csg	1766'	1370'	1370'	396'
Class A Cement Plug	2042'	1244'		
8 5/8" csg	1098'	Surface	Perforated @ 1000', 800' 600', 400', 200'	1098'
10" csg	153'	Surface		153'
Class A Cement Plug	1244'	Surface		

Received
Office of Oil and Gas
MAR 18 2016

Description of monument: Installed 6" x 4' monument with API # 47-033-01527.


and that the work of plugging and filling said well was completed on the 12th day of December, 2014.

NOTE:

And further deponents saith not.

Sworn and subscribe before me this 16th day of MARCY

My commission expires: Sept. 26, 2021



Notary Public

Affidavit reviewed by the Office of Oil and Gas Samuel D. [Signature] Title: OAG Inspector