

(+) DENOTES LOCATION OF WELL ON UNITED STATES TOPOGRAPHIC MAPS

FORM IV-6  
(8-78)  
**N49 N1WB**



DATE 1-9-, 1979  
 OPERATOR'S WELL NO. 2  
 API WELL NO. 47-033-1680  
 STATE COUNTY PERMIT

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL TYPE: OIL  GAS \_\_\_\_\_ LIQUID INJECTION \_\_\_\_\_ WASTE DISPOSAL \_\_\_\_\_  
 ( IF "GAS", PRODUCTION \_\_\_\_\_ STORAGE \_\_\_\_\_ DEEP \_\_\_\_\_ SHALLOW \_\_\_\_\_ )  
 LOCATION: ELEVATION \_\_\_\_\_ WATER SHED RIGHT FK BIG ECK CREEK  
 DISTRICT SARDIS COUNTY HARRISON  
 QUADRANGLE WALLACE 7.5'

SURFACE OWNER \_\_\_\_\_ ACREAGE \_\_\_\_\_  
 OIL & GAS ROYALTY OWNER \_\_\_\_\_ LEASE ACREAGE \_\_\_\_\_  
 LEASE NO. \_\_\_\_\_

PROPOSED WORK: DRILL \_\_\_\_\_ CONVERT \_\_\_\_\_ DRILL DEEPER \_\_\_\_\_ REDRILL \_\_\_\_\_ FRACTURE OR STIMULATE \_\_\_\_\_ PLUS OFF OLD FORMATION \_\_\_\_\_ PERFORATE NEW FORMATION \_\_\_\_\_ OTHER PHYSICAL CHANGE IN WELL (SPECIFY) \_\_\_\_\_

PLUG AND ABANDON \_\_\_\_\_ CLEAN OUT AND REPLUG \_\_\_\_\_  
 TARGET FORMATION \_\_\_\_\_ ESTIMATED DEPTH \_\_\_\_\_

WELL OPERATOR Pennco Oil Company DESIGNATED AGENT James A. Crews  
 ADDRESS P. O. Box 1588 ADDRESS P. O. Box 1588  
Parkersburg, WV 26101 Parkersburg, WV 26101

LATITUDE 39° 27' 30"

0  
0.41 S  
1.44 W

80° 27' 30"

LONGITUDE

7.5 OGIS topo location

7.5' loc, ✓ 15' loc 3.295  
(calc.) 3.67 N

Company Pennzoil 2

Farm Mary A. Bennett

Elev. 1131 top east.

Quad Wallace / Clkbrg NW

County Harrison

District Sardin

WELL LOCATION MAP

File No. 033-1680

**SOUTH PENN OIL COMPANY—COMPLETION**

SERIAL NO. \_\_\_\_\_ FARM Mary A. Bennett WELL NO. #2.  
 ELEVATION \_\_\_\_\_ N. 1 S. \_\_\_\_\_ E. 8 W. \_\_\_\_\_  
 LEASE NO. \_\_\_\_\_ ACRES 40  
 WATERS OF Big Elk.  
 DISTRICT Sardis COUNTY Harrison STATE W. Va.  
 DRILLING COMMENCED Oct 12, 1903 COMPLETED Dec 19, 1903 DEPTH 3061

SANDS	TOP	BOTTOM	ELEV. TOP	CASING
Pgm. COAL <del>4 1/2</del>	961			10 575
Big Lime	2185	2250		8 1/4 1446
Big Injun	2250	2355		6 9/8 2370
Stray	2974	3027		5 3/4
Gordon	3042	3061		
Pay	3054			

INITIAL PROD. 187 bbl per day SAND Gordon DEPTH 3054

GAS TEST \_\_\_\_\_  
 SHOT 8 times QUARTS 30-50-50 W \_\_\_\_\_ DEPTH 3053-53

REMARKS Depth of 1st shot not given.

REPORTED BY POLSON DISE ABANDONED \_\_\_\_\_  
P. O. 224-24-10-21

033-1680

STATE OF WEST VIRGINIA  
DIVISION OF ENVIRONMENTAL PROTECTION  
SECTION OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: TRIMBACH, WILLIAM&DOLORES Operator Well No.:W. A. BENNETT 2  
LOCATION: Elevation: 1,120.00 Quadrangle: WALLACE  
District: SARDIS County: HARRISON  
Latitude: 2120 Feet South of 39 Deg. 27 Min. 30 Sec.  
Longitude 7560 Feet West of 80 Deg. 27 Min. 30 Sec.

Well Type: OIL \_\_\_\_\_ GAS —X—


Company: Ross & Wharton Gas Company  
Rt. 6, Box 123  
Buckhannon, WV 26201

Coal Operator NA  
or Owner \_\_\_\_\_

Agent: Mike Ross

Coal Operator NA  
or Owner \_\_\_\_\_

Permit Issued: 04/19/99



AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Upshur ss:

Robert L. Wharton and Don Elmer being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and Tim Bennett Oil and Gas Inspector representing the Director, say that said work was commenced on the 29th day of April, 1999, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Gel	3000	2300	1446 of 6 5/8"	924'
Cement	3000	2800	630 of 8"	916'
Gel	2800	2420	22' 6" of 10"	552' 6"
Cement	2420	2320		
Gel	2320	1525		
Cement	1525	1380		
Gel	1380	1000		
Cement	1000	900	Cut holes @ 990,	Coal 961-920
Gel	900	654		

Description of monument: 6 in. pipe 36 in. high  
554, Gel 554-180, Cement 180 - 0


and that the work of plugging and filling said well was completed on the 20th day of May, 1999.

And further deponents saith not.

Don Elmer  
R. L. Wharton

Sworn and subscribe before me this 2nd day of May, 1999  
My commission expires: 11-03-03

Elene Murray  
Notary Public



Gas Inspector: Tim Bennett 6-7-99

JUL 12 1999

HAR 1620-P