

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: CAMPBELL, STEVEN W., ET UX Operator Well No.: ALBERT SHINN 7

LOCATION: Elevation: 1133.07' Quadrangle: CLARKSBURG
District: CLAY County: HARRISON
Latitude: _____ Feet South of _____ Deg. _____ Min. _____ Sec.
Longitude: _____ Feet West of _____ Deg. _____ Min. _____ Sec.

RECEIVED
Office of Oil and Gas

NOV 09 2018

WV Department of
Environmental Protection

SEE ATTACHED GPS LOCATION FORM
Well Type: OIL _____ GAS x

Company EnerVest Operating, LLC Coal Operator Consolidation Coal Company
300 Capitol St., Suite 200 or Owner 1000 CONSOL Energy Dr.
Charleston, WV 25301 Cannonsburg, PA 15317-6506
Agent Barry Lay Coal Operator _____
Permit Issued Date 11/29/2011 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Harrison ss:

Rick Hanifan and Bill Hess being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 19th day of December, 2011, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Cement	2682'	2500'		
Cement	1262'	1036' **	1263' of 4 1/2" csg	1537' of 4 1/2" csg
Cement	545'	395	Holes shot @ 470' & 183'	
Cement	150	0		1043' of 8 5/8" csg
6% Gel	between cement plugs			
Install Monument with API# and Date				


** Rig tagged plug @ 964'

Description of monument: 4' - 8 5/8" CSG vented w/API# and Date and that the work of plugging and filling said well was completed on the 28th day of December, 2011.

And further deponents saith not.

[Signature]
Rick Hanifan

Sworn and subscribe before me this 9th day of November, 2018



My commission expires: 5/3/2022

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: _____ Title: _____