

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

511

WELL RECORD

Permit No. **6407**


Oil or Gas Well **OIL**
(KIND)

Company **South Penn Natural Gas Company**
Address **Union Trust Bldg. Parkersburg, W. Va.**
Farm **J. W. Edgell** Acres **40**
Location (waters) **Big Rock Camp**
Well No. **1** Elev. **1103.15**
District **Sardis** County **Harrison**
The surface of tract is owned in fee by **Asa L. Edgell**
R.F.D.No. 2, Address **Wallace, W. Va.**
Mineral rights are owned by **J. W. Edgell**
R.F.D.No. 1, Address **Malta, Ohio.**
Drilling commenced **Aug. 24, 1905**
Drilling completed **Oct. 14, 1905**
Date shot **Oct. 14-1905** Depth of shot **--**
~~Sep: 13-1912~~
Open Flow /10ths Water in **--** Inch
/10ths Merc. in **--** Inch
Volume **--** Cu. Ft.
Rock Pressure **--** lbs **--** hrs.
Oil **20** bbls., 1st 24 hrs.
Fresh water **-** feet **-** feet
Salt water **-** feet **-** feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16.			Kind of Packer -
13.			-
10.	305'		Size of -
8 1/4	1419'		-
6 5/8	2301'		Depth set -
5 3/16			-
3.			Perf. top -
2.			Perf. bottom -
Liners Used			Perf. top -
Cond.	16'		Perf. bottom -

CASING CEMENTED **-** SIZE **-** No. Ft. **-** Date **-**
COAL WAS ENCOUNTERED AT **875** FEET **48** INCHES
- FEET **-** INCHES **-** FEET **-** INCHES
- FEET **-** INCHES **-** FEET **-** INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Pittsburgh Coal			875	879			
Little Dunkard			1340	1385			
Big Dunkard			1405	1430			
Gas Sand			1660	1675			
Salt Sand			1760	1820			
Maxon Sand			1920	1960			
Big Lime			2105	2165			
Big Injun			2170	2270			
Fifty Foot Sand			2720	2760			
Boulder Sand			2820	2840			
Stray & 30' Sand			2854	2924			
Gordon Sand			2939	2962			
					Gas Oil	2726 2954	
Total Depth				2971			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date **May 15**, 194**1**

APPROVED **South Penn Natural Gas Company** Owner

By *Elton Young* Land Agent.
(Title)

