

0.17S  
0.17W

New Location   
 Drill Deeper   
 Abandonment  3117

Map Sheet 41 Squares S3E11FB.535P.26-27

Company Hope Natural Gas Co.  
 Address Clarksburg, W. Va.  
 Farm R. G. Robinson  
 Tract \_\_\_\_\_ Acres 182 Lease No. 8335  
 Well (Farm) No. \_\_\_\_\_ Serial No. See Above  
 Elevation (Spirit Level) See Above  
 Quadrangle Clarksburg  
 County Harrison District Eagle  
 Engineer W.M. Bowers  
 Engineer's Registration No. 900  
 File No. \_\_\_\_\_ Drawing No. \_\_\_\_\_  
 Date August 30, 1945 Scale 1" = 4' CP

STATE OF WEST VIRGINIA  
 DEPARTMENT OF MINES  
 OIL AND GAS DIVISION  
 CHARLESTON

WELL LOCATION MAP  
 FILE NO. HAR-891-A-#3

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.

-- Denotes one inch spaces on border line of original tracing.



STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

734

WELL RECORD

Permit No. 841-A


Oil or Gas Well \_\_\_\_\_  
(KIND)

Company Hope Natural Gas Company.  
 Address 445 West Main St. Clarksburg, W. Va.  
 Farm R.C. Robinson Acres 182  
 Location (waters) 3117 (2)  
 Well No. Eagle Elev. 1290  
 District Harrison County Harrison  
 The surface of tract is owned in fee by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced November 11, 1913  
 Drilling completed January 2, 1914  
 Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
 With \_\_\_\_\_  
 Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
 \_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
 Fresh water none recorded feet \_\_\_\_\_ feet  
 Salt water none recorded feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	<b>471</b>	<b>471</b>	Size of
8 1/4			
6 5/8	<b>1785</b>	<b>1785</b>	Depth set
5 3/16			
3			Perf. top
2	<b>2450</b>	<b>2450</b>	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED 10" SIZE 471 No. Ft. 1913 Date \_\_\_\_\_  
 COAL WAS ENCOUNTERED AT 40 FEET 48 INCHES  
408 FEET 72 INCHES FEET INCHES  
 FEET INCHES FEET INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Native coal			40	44			
Pittsburgh Coal			408	414			
Little Dunkard			805	840			
Big Dunkard			935	995			
Gas sand			1130	1210			
First Salt			1235	1255			
Second Salt			1290	1440			
Maxon			1515	1570			
Little Lime			1710	1732			
Pencil cave			1732	1757			
Big Lime			1757	1778			
Big Injun			1778	1893			
Gantz			2250	2257	gas	2252	
Fifty foot			2290	2320			
Thirty Foot			2390		gas	2450	
Total depth				2450			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date August 31, 1945., 194

APPROVED Hope Natural Gas Company., Owner

By [Signature] (Title)  
 Ass't. to Gen. Sup't.

