



816

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

WELL RECORD

Permit No. HAR-973-A


Oil or Gas Well Gas
(KIND)

Company Hope Natural Gas Company
 Address 445 W. Main St. Clarksburg, W. Va.
 Farm Jas. P. Eoring Acres 166
 Location (waters) _____
 Well No. 8052 Elev. 1166
 District Union County Harrison
 The surface of tract is owned in fee by Edna Eoring
 Address Wolf Summit, W. Va.
 Mineral rights are owned by _____
 Address _____
 Drilling commenced 4-4-1910
 Drilling completed 5-13-1910
 Date Shot 5-15-17 From 2998 To 3010 Fifth Sand
 With 1-3-22 30 and 30 qts.
 Open Flow _____ /10ths Water in _____ Inch
 _____ /10ths Merc. in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure _____ lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water None recorded feet _____ feet
 Salt water None recorded feet _____ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packer
13			
10	186	None	Size of
8 1/4	919	919	
6 5/8	1450	1450	Depth set
5 3/16	2109	2109	
3			Perf. top
2	3028	3028	Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
Not cemented
 COAL WAS ENCOUNTERED AT No coal FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Little Dunkard			380	410			
Big Dunkard			500	530			
Gas Sand			752	780			
First Salt			825	870			
Second Salt			895	930			
Maxon			1135	1197	Gas	1153 - Show	
Pencil Cave			1375	1385 (1395)			
Big Lime			1385	1446			
Big Injun			1446	1531			
Squaw			1575	1582			
Berea			1735	1650			
Fifty Foot			1868	1918	Gas	1895	
Thirty Foot			1972	1995	Gas	1976-1981	
Gordon Stray			2083	2091			
Gordon			2092	2133	Gas	2113	
Fifth			2300	2311	Gas	2301-2307	
Speechley			2997	3008	Gas	2999	
Total depth				3025			



Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks

Date April 23, 1946

APPROVED Hope Natural Gas Company, Owner

By J. A. Clark Gen. Supt.

By JAC (Title)

NOT LOCATED

JAS. P. BORING NO. 8052 WELL.

973A

Union District, Harrison County, W. Va.
By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.
Abandoned under permit Har-.....-A.

On 166 acres.

Elevation, 1166' L.

Surface owned by Edna Boring, Wolf Summit, W. Va., Route No. 2.

Drilling commenced April 4, 1910; completed May 13, 1910.

Shot May 15, 1917, in Fifth Sand; shot Jan. 3, 1922, at 3010';
with 30 and 30 qts.

Water, none recorded.

10" casing, 186' (pulled); 8 $\frac{1}{2}$ "⁸, 919'; 6 $\frac{3}{8}$ "⁸, 1450'; 5 $\frac{1}{2}$ "⁸, 2109'; 2" tubing,
3025'.

Casing not cemented.

No coal was encountered.

Gas well. Abandonment reported to Dept. of Mines April 23, 1946.

Record to RCT from Mrs. Griffith July 16, 1946. Old File No. 816.

	Top.	Bottom.
Little Dunkard Sand	380	- 410
Big Dunkard Sand	500	- 530
Gas Sand	752	- 780
First Salt Sand	825	- 870
Second Salt Sand	895	- 930
Marion Sand (gas show, 1153')	1135	- 1197
Pencil Cave	1375	- 1385
Big Lime	1385	- 1446
Big Injun Sand	1446	- 1531
Squaw Sand	1575	- 1582
Berea Sand	1735	- 1650
Fifty-foot Sand (gas, 1895')	1868	- 1918
Thirty-foot Sand (gas, 1976-1981')	1972	- 1995
Garden Stray Sand	2083	- 2091
Garden Sand (gas, 2113')	2092	- 2133
Fifth Sand (gas, 2301-2307')	2300	- 2311
Speechley Sand (gas, 2999')	2997	- 3008
Total depth		3025