

LATITUDE 39° 12' 30"

11° 00' 52" 08 LONGITUDE



2.27N
1.08W

7'5 OGIS topo location

7.5' loc _____

15' loc _____
(calc.) _____

Company HNG. Co (7848)

Farm Joseph Chevrant

Quad West Milford 7 1/2

County Harrison

District Grant

WELL LOCATION MAP

File No. 033-31108

JOSEPH CHEUVRONET NO. 7848 WELL.

1108A

Grant District, Harrison County, W. Va.

By Hope Natural Gas Co., 445 W. Main St., Clarksburg, W. Va.

Abandoned under permit Har-.....-A?

On 200 acres.

Elevation, 995' L.

Purchased well.

No water recorded.

10" casing, 226'; 8 $\frac{1}{2}$ " 961'; 6 $\frac{1}{2}$ " 1620'; 5 $\frac{1}{2}$ " 2361'; 3" tubing, 2753'.

Casing not cemented.


Coal was encountered at 105-109, 514-517, and 610-615'.

Gas well. Abandonment reported to Dept. of Mines Oct. 1, 1947.

Record to RCT from Mrs. Griffith March 24, 1948. Old File No. 928.

(encl + 525A)

	Top.	Bottom.
Coal	105	- 109
Coal	514	- 517
Big Dunkard Sand	610	- 645
Coal	653	- 660
First Salt Sand	668	- 740
Second Salt Sand	765	- 785
Maxton Sand (gas, 955')	950	- 970
Little Lime	1115	- 1127
Big Lime (show gas, 1165')	1155	- 1209
Big Injun Sand (gas, 1254')	1209	- 1314
Gentz Sand	1635	- 1665
Gorden Sand (show gas, 1743')	1726	- 1743
Fifth Sand (gas, 2049-2059')	2049	- 2059
Speechley Sand (gas, 2740')	2739	- 2744
Total depth		2753



WELL RECORD

Permit No. 1111
 Company Hope Natural Gas Company
 Address 443 West 6th St. St. Paul, Minn.
 Farm Joseph Cheuvront Acres 800
 Location (waters): _____
 Well No. 7148 Elev. 950
 District Grant County Harrison

Oil or Gas Well _____
 (check)

The surface of tract is owned in fee by _____
 Address _____
 Mineral rights are owned by _____
 Address _____

Drilling commenced performed
 Drilling completed _____
 Date Shot _____ From _____ To _____
 With _____
 Open Flow 10ths Water in Inch _____
10ths Merc in Inch _____
 Volume perc. used Cu Ft _____
 Rock Pressure _____ lbs _____ hrs
 Oil _____ bbls. 1st 24 hrs. _____
 Fresh water none recorded feet _____
 Salt water none recorded feet _____

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			
16			Kind of Packers
18			
10	226	226	Size of
8 1/2	961	961	
6 1/2	1620	1620	Depth set
5 1/2	2361	2361	
3	2733	2733	Perf. top
2			Perf. bottom
			Perf. top
			Perf. bottom

CASING CEMENTED	NET SIZE	No Ft.	Date
COAL WAS ENCOUNTERED AT			
		105 FEET 68	INCHES
	514 FEET 36	INCHES	610 FEET 60
	FEET	INCHES	FEET
		INCHES	INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Coal			105	109			
Coal			514	517			
Coal			610	645			
Coal			653	660			
First Salt			668	740			
Second Salt			765	785			
Mazon			950	970	gas	955	
Little Linn			1115	1127			
Big Linn			1155	1209			
Sig Linn			1209	1314	oil gas	1165	
Ganta			1630	1665	gas	1254	
Gordon			1736	1743	oil gas	1743	
Firth			2049	2065	gas	2049	2065
Speedway			2739	2744	gas		
Total depth				2733			

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE AND ONE COPY TO BE FILED IN THE WELL OPERATOR AND THE OTHER COPY AND EXTRA COPIES IF REQUIRED SHOULD BE MAILED TO EACH COAL OPERATOR AT THEIR RESPECTIVE ADDRESSES.

NO COAL OPERATIONS
COAL OPERATOR OR OWNER

ADDRESS

COAL OPERATOR OR OWNER

ADDRESS

NAME OF PROPERTY OWNER

ADDRESS

Hope Natural Gas Company,
NAME OF WELL OPERATOR

640 West Main St., CHARLESTON, W. Va.
COMPLETE ADDRESS

12-10-47

WELL AND LOCATION

194

Town,

District

HARRISON

County

Well No. 48

Farm

Joseph Clewford,

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,

County of Harrison

James W. Himerman

and William P. Flist,

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Hope Natural Gas Company well operator, and participated in the work of plugging and filling the above well that said work was commenced on the 20th day of October 1947 and that the well was plugged and filled in the following manner

BAND OR ZONE RECORD	FORMATION	CONTENT	FILLING MATERIAL		PLUGS USED	CASING	
			FROM	TO		SIZE	DEPTH IN FEET
Coal	105-109	Clay	2753	2719			
Coal	514-517	Cement	2719	2709	10' Cement	3" Tubing.	
Lime	1155-1209	Bridged	2099			2753	None.
Gas	1166	Clay	2099	2029			
Sand	1726-1743	Cement	2029	2019	10' Cement	5 1/2" casing.	
Gas	1743	Bridge	1773			1976.6	384.6
5th.	2042-2069	Clay	1773	1706			
Gas	2042-2069	Cement	1706	1696	10' Cement	7" casing.	
Sphly	2732-2744	Bridge	1630			1286.6	333.7
Gas	2740-2742	Cement	1630	1620	10' Cement	8 5/8" casing.	
Total depth	2753	Bridged	1344			961	None
		Clay	1344	1200			
		Cement	1200	1190	10' Cement	10 1/2" casing.	
		Bridged	1000				
		Cement	1000	990	10' Cement		
		Clay	990	930			
		Cement	930	920			
		Bridged	750				
		Clay	750	690			
		Cement	690	633			

DESCRIPTION OF MONUMENT

8"x5" concrete monument with 1 7/8" embedded in same set in concrete pad over hole.

and that the work of plugging and filling said well was completed on the 10 day of December

And further deponants say

day of