

Union District, Harrison County, W. Va.

1219A

By William Moses, Salem, W. Va.

Abandoned under permit Har-.....-A?

On 51.61 acres.

Elevation.....

Surface owned by William Moses, Salem, W. Va., and minerals by

L. E. Claghorn, Clarksburg, W. Va.

Drilling commenced April 15, 1919; completed May 29, 1919.

10" casing, 136'; 8 $\frac{1}{4}$ " , 1088'; 6 $\frac{5}{8}$ " , 1585'; 2" tubing, 2348'; all left in.

Coal was encountered at 25-30'.

Oil well. Abandonment reported to Dept. of Mines (stamped) June 29, 1948.

Record to RCT from Mrs. Griffith July 23, 1948. Old File No. 983.

	Top.	Bottom.
Pittsburgh Coal	25	- 30
Little Dunkard Sand	440	- 460
Big Dunkard Sand	530	- 570
1st Salt Sand	700	- 765
2nd Salt Sand	820	- 1028
Little Lime	1470	- 1490
Big Lime	1505	- 1560
Big Injun Sand	1560	- 1682
Fifty-foot Sand	2020	- 2092
Thirty-foot Sand	2100	- 2150
Garden Sand	2326	- 2348
Total depth		2365



703

STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

WELL RECORD

Permit No. HAR-1219-A

Oil or Gas Well oil  
(KIND)

Company <u>William Moses</u>	Casing and Tubing	Used in Drilling	Left in Well	Packers
Address <u>Salem, W. Va</u>	Size			
Farm <u>W. B. Sawyer</u> Acres <u>5.61</u>	16			Kind of Packer
Location (waters)	13			
Well No. <u>6062</u> Elev.	10		<u>136</u>	Size of
District <u>Union</u> County <u>Harrison</u>	8 1/4		<u>1088</u>	Depth set
The surface of tract is owned in fee by <u>William Moses</u>	6 5/8		<u>1585</u>	
Address <u>Salem, W. Va.</u>	5 3/16			
Mineral rights are owned by <u>J. C. Coppen</u>	3			Perf. top
Address <u>Elkhart, W. Va.</u>	2		<u>2348</u>	Perf. bottom
Drilling commenced <u>4/15/19</u>	Liners Used			Perf. top
Drilling completed <u>5/12/19</u>				Perf. bottom
Date Shot From To				
With				
Open Flow /10ths Water in Inch				
/10ths Merc. in Inch				
Volume Cu. Ft.				
Rock Pressure lbs. hrs.				
Oil bbls., 1st 24 hrs.				
Fresh water feet feet				
Salt water feet feet				


CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT 25 FEET \_\_\_\_\_ INCHES

\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
<u>Pitts Coal</u>			<u>25</u>	<u>30</u>			
<u>S. Lunkard</u>			<u>440</u>	<u>460</u>			
<u>B. Lunkard</u>			<u>530</u>	<u>570</u>			
<u>1st Salt</u>			<u>700</u>	<u>765</u>			
<u>2nd Salt</u>			<u>820</u>	<u>1028</u>			
<u>S. Lime</u>			<u>1470</u>	<u>1490</u>			
<u>B. Lime</u>			<u>1505</u>	<u>1560</u>			
<u>B. Trjurn</u>			<u>1560</u>	<u>1682</u>			
<u>Fifty foot</u>			<u>2020</u>	<u>2092</u>			
<u>Thirty foot</u>			<u>2100</u>	<u>2150</u>			
<u>Gordon</u>			<u>2326</u>	<u>2348</u>			
<u>Total depth</u>			<u>2365</u>				



44 23 10 10