

3.05S
1.38W

New Location..
 Drill Deeper.....
 Abandonment.....

Company CARNEGIE NATURAL GAS
 Address PITTSBURGH Pa.
 Farm G.C. CUNNINGHAM
 Tract _____ Acres 37 Lease No. E7763-77
 Well (Farm) No. 2 Serial No. E 918
 Elevation (Spirit Level) 1484'
 Quadrangle CLARKSBURG S.W.
 County HARRISON District SARDIS
 Engineer John O. ...
 Engineer's Registration No. 1850
 File No. _____ Drawing No. _____
 Date 9-9-58 Scale 1" = 20 Poles

STATE OF WEST VIRGINIA
 DEPARTMENT OF MINES
 OIL AND GAS DIVISION
 CHARLESTON

WELL LOCATION MAP
 FILE NO. HAR-1680-A

+ Denotes location of well on United States Topographic Maps, scale 1 to 62,500, latitude and longitude lines being represented by border lines as shown.
 - Denotes one inch spaces on border line of original tracing.



1556

STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

Robinson

WELL RECORD

Permit No. 1680A

WELL TO BE ABANDONED



Oil or Gas Well GAS
(KIND)

Company Carnegie Natural Gas Company
 Address 1015 Frick Building, Pittsburgh 19, Pa.
 Farm G. C. Cunningham Acres 37
 Location (waters) _____
 Well No. 2-918 Elev. 1484
 District Sardis County Harrison
 The surface of tract is owned in fee by Compass Coal Co.
Dola Address W. Va.
 Mineral rights are owned by Mrs. L. A. Cunningham,
5538 Tremont Street Address Dallas, Texas
 Drilling commenced 4-29-19
 Drilling completed 7-10-19
 Date Shot _____ From _____ To _____
 With _____
 Open Flow 80/10ths Water in 2 Inch
 _____ /10ths Merc in _____ Inch
 Volume _____ Cu. Ft.
 Rock Pressure 250 lbs. _____ hrs.
 Oil _____ bbls., 1st 24 hrs.
 Fresh water 1120 feet _____ feet
 Salt water _____ feet _____ feet

| Casing and Tubing | Used in Drilling | Left in Well | Packers |
|-------------------|------------------|--------------|----------------|
| Size | | | Kind of Packer |
| 16 | | | |
| 13 | | | |
| 10 | 740 | 740 | Size of |
| 8 1/4 | 1336 | 1336 | |
| 6 5/8 | 2031 | 2031 | Depth set |
| 5 3/16 | | | |
| 3 | | | Perf. top |
| 2 | 2944 | 2944 | Perf. bottom |
| Liners Used | | | Perf. top |
| | | | Perf. bottom |

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____
 COAL WAS ENCOUNTERED AT 693 FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES
 _____ FEET _____ INCHES FEET _____ INCHES

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|-----------------|-------|--------------|------|--------|-------------------|-------------|---------------------------|
| Pittsburgh Coal | | | 693 | 696 | Water | 1120 | <i>[Handwritten mark]</i> |
| Little Dunkard | | | 1105 | 1135 | | | |
| Big Dunkard | | | 1180 | 1210 | | | |
| Gas Sand | | | 1460 | 1510 | | | |
| 1st Salt Sand | | | 1535 | 1553 | | | |
| Maxon Sand | | | 1924 | 1972 | | | |
| Little Lime | | | 1990 | 1996 | | | |
| Big Lime | | | 2004 | 2058 | | | |
| Big Injun | | | 2058 | 2111 | | | |
| Fifty Foot | | | 2605 | 2627 | | | |
| Thirty Foot | | | 2675 | 2695 | Gas | 2866 -2871 | |
| Gordon Stray | | | 2805 | 2845 | | | |
| Gordon Sand | | | 2852 | 2887 | | | |
| Fourth Sand | | | 2912 | 2935 | | | |
| Total Depth | | | | 2944 | | | |



DEC 20 1958

| Formation | Color | Hard or Soft | Top | Bottom | Oil, Gas or Water | Depth Found | Remarks |
|-----------|-------|--------------|-----|--------|-------------------|-------------|---------|
| | | | | | | | |

Date September 15, 19 58

APPROVED CARNEGIE NATURAL GAS COMPANY, Owner

By J. A. Walker
 (Title) Land Agent