

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Kay, John P. Operator Well No.: DEK-38

LOCATION: Elevation: 814' Quadrangle: Ravenswood

District: Ravenswood County: Jackson

Latitude: 38.8821207534208 Feet South of 38 Deg. 55 Min. 0 Sec.

Longitude: -81.803644545792 Feet West of -81 Deg. 45 Min. 30 Sec.

RECEIVED
Office of Oil and Gas

APR 2 2021

WV Department of
Environmental Protection

Well Type: OIL _____ GAS X

Company NYTIS EXPLORATION CO LLC Coal Operator No Declaration
PO BOX 8 or Owner _____
RAVENSWOOD, WV 26164 _____
Agent Jeff Mast Coal Operator _____
Permit Issued Date 2/16/21 or Owner _____

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Jackson ss:

Melvin Myers and James Pursley being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 15th day of March, 2021, and the well was plugged and filled in the following manner:


TYPE	FROM	TO	PIPE REMOVED	LEFT
10 sks C1A cement	4516'	4320'	4499' of 2 3/8" tbg	0
20 sks C1A cement	3867'	3617'	1500' of 4 1/2" csg	3115'
30 sks C1A cement	2480'	2200'	300' of 7" csg	2077'
24 sks C1A cement	1556'	1400'		
20 sks C1A cement	814'	714'		
50 sks C1A cement	350'	194'		
38 sks C1A cement	100'	Surface		

Description of monument: 7" casing with API # 36" above ground and that the work of plugging and filling said well was completed on the 23rd day of March, 2021.

And further deponents saith not. [Signatures]

Sworn and subscribe before me this 29th day of March, 2021

My commission expires Sept. 18, 2022
Sandra L. Messer
Notary Public



Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: 3-30-21