

039

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS



ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Frank A. Hardy Operator Well No.: 4066

LOCATION: Elevation: GPS 1144 Quadrangle: Charleston West C6

District: Louden County: Kanawha

Latitude: gps 4231397.2 Feet South of _____ Deg. _____ Min. _____ Sec.

Longitude: gps 443315.5 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS X

Company Pillar Energy LLC Coal Operator _____
1244 Martins Branch rd or Owner _____
Charleston Wv 25312 _____

Agent Jeff Isner Coal Operator _____
Permit Issued Date 06-28-2021 or Owner _____

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of Roane ss:

Gary Rexroad and Darrell Shamblin being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
latex cement	5455'	5207' tagged	1764' of 41/2" casing	3712' of 41/2" casing
6% gel	5207'	1855'	331' of 85/8" casing	1393' of 85/8" casing
latex cement	1855'	1652' tagged		ripped holes in 85/8" casing
6% gel	1652'	1635'		at 1575', 1286', 1152'
cement	1635'	1451' tagged		103/4" casing cemented inside of 133/8"
6% gel	1451'	1289'	6% gel 1048'-408'	could not pull
cement	1289'	1048'	cement 408'-surface	

Description of monument: 7" OD X 40" above ground level and that the work of plugging and filling said well was completed on the 2nd day of August, 2021.

And further deponents saith not. Gary W. Rexroad
Darrell Shamblin



Sworn and subscribe before me this 4th day of August, 2021

My commission expires: July 6, 2025
Robin Young
Notary Public

Affidavit reviewed by the Office of Oil and Gas: August 16-21 Title: Inspector Delores

08/27/2021

DATE

VISITS

7-26-21

Cut Trees preparing location to Plug

7-27-21

TOH to 5455 mixed 10 SKs gel and 20 SKs cement with latex Displace with 14 BBL gel

7-28-21

Tagged plug @ 5207ft found free part @ 1764ft and pulled 4.5 CSY

7-29-21

Ran in Hole to 2550 ft mixed 17 SKs gel TOH to 1855 mixed 82 SKs Cement with latex Displace 4 BBL

7-30-21

Tagged plug at 1652 TOH 1575 Ripped Holes mixed 60 SKs Cement TOH to 1289 mixed 75 SKs Pent TOH 408ft mixed 140 SKs Cement

8-2-21

Tagged at 1231 mixed 128 SKs to Surface