

STATE OF WEST VIRGINIA
 DEPARTMENT OF ENVIRONMENTAL PROTECTION
 OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATED, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: BLUE CREEK COAL + LAND Operator Well No.: 809033

LOCATION: Elevation: 1,246' Quadrangle: CLENDENIN, WV 7.5'
 District: ELK County: KANAWHA
 (N) Latitude: 38.3754110° Feet South of _____ Deg. _____ Min. _____ Sec.
 (W) Longitude: 81.3322674 Feet West of _____ Deg. _____ Min. _____ Sec.

Well Type: OIL _____ GAS

Company: CHESAPEAKE APPALACHIA, LLC Coal Operator BLUE EAGLE LAND, LLC
PO BOX 18496 or Owner ATTN: DAVE HANCOCK
OKLAHOMA CITY, OK 73154-0496 PO BOX 58370
 Agent: JESSICA GREATHOUSE Coal Operator CHARLESTON, WV 25358
 or Owner

Permit Issued Date: 07-07-2015

PATRIOT COAL
63 CORPORATE CENTER DRIVE
P.O. BOX 1001
SCOTT DEPOT, WV 25560

AFFIDAVIT

STATE OF WEST VIRGINIA,
 County of ROANE ss:

RICHARD D. MOORE and TOMMY ESTEP being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 13TH day of APRIL, 2016 and the well was plugged and filled in the following manner:

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|---|-------|-------|-----------------|----------------|
| CEMENT | 2210' | 1810' | | |
| CEMENT | 1734' | 1634' | 1700' OF 4 1/2" | 557' OF 4 1/2" |
| CEMENT | 1250' | 1000' | | |
| CEMENT | 850' | 750' | 380' OF 8 5/8" | 427' OF 8 5/8" |
| CEMENT | 375' | 175' | | |
| CEMENT | 100' | 0' | | |
| <u>* 6% GEL BETWEEN ALL CEMENT PUGS</u> | | | | |


Description of monument: 8" CASING 36" ABOVE GROUND w/ API TAG and that the work of plugging and filling said well was completed on the 27TH day of APRIL, 2016.

And further deponents saith not. Richard D Moore

Tommy Estep

Sworn and subscribe before me this 11th day of March, 2016

My commission expires: Feb 16, 2019
 Notary Public



Affidavit reviewed by the Office of Oil and Gas: Dennis Chapman
 Inspector Specialist

06/10/2016