

*Original*

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS



ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Black Band Coal Operator Well No.: 5 (3969)

LOCATION: Elevation: GPS 1239' Quadrangle: Charleston West C6

District: Loudon County: Kanawha

Latitude: 38.237004 Feet South of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Longitude: 81.639240 Feet West of \_\_\_\_\_ Deg. \_\_\_\_\_ Min. \_\_\_\_\_ Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company	<u>Pillar Energy, LLC</u>	Coal Operator	_____
	<u>1244 Martins Branch Rd.</u>	or Owner	_____
	<u>Charleston, Wv 25312</u>		_____
Agent	<u>Jeff Isner</u>	Coal Operator	_____
		or Owner	_____
Permit Issued Date	<u>06-07-2021</u>		_____

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Roane ss:

Gary W. Rexroad and Darrell Shamblin being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 7th day of July, 2021, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
latex cement	5603'	5347'	1545' of 41/2" casing	4076' of 41/2" casing
6% Gel	5347'	3315'	200' of 65/8" casing	1379' of 65/8" casing
latex cement	3315'	2570'		356' of 10" casing
6% gel	2570'	2550'	cement 1261' to 1144'	
latex cement	2550'	1697'	6% gel 1144' to 952'	cement 408' to surface
cement	1697'	1352'	cement 952' to 847'	
6% gel	1352'	1261'	6% gel 847' to 408'	

Description of monument: 7" OD X 40" above ground with API # welded on and that the work of plugging and filling said well was completed on the 23rd day of July, 2021.

And further deponents saith not. Gary W. Rexroad  
Darrell Shamblin



Sworn and subscribe before me this 26<sup>th</sup> day of July, 2021

My commission expires: July 6, 2025  
Robin Young  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature] Title: Inspector **08/27/2021**