

ORIGINAL

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

39-04529

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Shonk Land Company Operator Well No.: Shonk 13
LOCATION: Elevation: 1,229' Quadrangle: Sylvester
District: Cabin Creek County: Kanawha
Latitude: 12.787 Feet South of 38 Deg. 07 Min. 30 Sec.
Longitude: 3,434 Feet West of 81 Deg. 30 Min. 00 Sec.

Well Type: OIL GAS

Company: Panther LLC.
500 Lee Street, East Suite 900
Charleston, WV 25301

Coal Operator _____
or Owner _____
Coal Operator _____
or Owner _____

Agent: Gary E. Acord

Permit Issued Date: 10/09/2013

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Kanawha ss:

Josh Dotson and Gary E. Acord being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well, and say that said work was commenced on the 25th day of October, 2013, and that the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Skyline Cleaned Out	Surface	2,833'	1100' of 4 1/2" casing	8 5/8" casing 0'-1219'
Nabors Cemented	2950'	1230'	Class A Cement	4 1/2" casing 1100'-2904'
Appalachian Well Elog Caliper	Collar	Indicator	Top coal 705' Bottom coal 710'	2 3/8" tubing 1370' to 1600'
Appalachian Well Perforate	40 Holes:	702.5 - 712.5	4 Holes: 910', 860', 810', 760', 720', 715',	
Skyline Services ran tubing	Surface	2833'	700', 695', 655', 605'	
Nabors Cemented	1230'	281'	240 Sacks Super Tropic	
Nabors Cemented	281'	Surface	Class A Cement	
This well is plugged to	101c	Standards		

Description of monument: Erect monument with API# 47-039-04529 and that the work of plugging and filling said well was completed on the 5th day of November, 2013.


And further deponents saith not.

[Signature]
[Signature]

Sworn and subscribe before me this 6 day of November, 2013
My commission expires: 2/14/2022

[Signature]
Notary Public

Affidavit reviewed by the Office of Oil and Gas: [Signature]
Title: Inspector, Oil & Gas



NOV 07 2013

11/08/2013
WV Department of
Environmental Protection