



Elk District, Kanawha County, W. Va.

By Virginian Gasoline & Oil Co., Box 1256, Charleston, W. Va.

On 30 acres, on Left Fork of Finch Creek.

Elevation, 700' L.

Surface owned by G. W. Thumm, Agent, Charleston, W. Va.

Drilling commenced May 18, 1912; completed, June 25, 1912.

Shot June 24, 1912, at 1754'.

Oil, 200 bbls., 1st 24 hrs.

10" casing, 33'; 8 $\frac{1}{4}$ ", 498' (pulled); 6-5/8", 1530'.

Oil well. Abandonment reported to Dept. of Mines May 5, 1938.

Record to RCT from Mrs. Griffith May 27, 1938.

	Top.	Bottom.
Sand	0	- 405
Slate	405	- 450
Sand	450	- 480
Slate	480	- 550
Sand	550	- 600
Slate and shell	600	- 800
Salt Sand	800	- 910
Slate and shell	910	- 1340
Maxton Sand	1340	- 1400
Slate and shells	1400	- 1445
Little Lime	1445	- 1470
Slate and shell	1470	- 1510
Big Lime	1510	- 1660
Big Injun Sand	1660	- 1700
Slate shells	1700	- 1743
Oil sand (Weir)	1743	- 1768
Total depth		1768

WEST VIRGINIA DEPARTMENT OF MINES  
OIL AND GAS DIVISION

646

WELL RECORD

Permit No. KAA-242-A


Oil or Gas Well Oil  
(Kind)

Company Virginian Gasoline & Oil Co.  
 Address Box 1256, Charleston, W. Va.  
 Farm J. F. Thumm Hrs. Acres 30  
 Location (waters) Left Fork, Pinch Creek  
 Well No. 2895 Elev. 700.0  
 District Elk County Kenawha  
 The surface of tract is owned in fee by G. W. Thumm, Agt.  
 Address Charleston, W. Va.  
 Mineral rights are owned by \_\_\_\_\_  
 Address \_\_\_\_\_  
 Drilling commenced May 18, 1912  
 Drilling completed June 25, 1912  
 Date shot June 24, 1912 Depth of shot 1754  
 Open Flow /10ths Water in \_\_\_\_\_ Inch  
 /10ths Merc. in \_\_\_\_\_ Inch  
 Volume \_\_\_\_\_ Cu. Ft.  
 Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
 Oil 200 bbls., 1st 24 hrs.  
 Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
 Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10	33	33	Size of
8 1/4	498	--	
6 5/8	1530	1530	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. FT. \_\_\_\_\_ Date \_\_\_\_\_  
 COAL WAS ENCOUNTERED AT \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
 \_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil Gas or Water	Depth Found	Remarks
Sand			0	405			
Slate			405	450			
Sand			450	480			
Slate			480	550			
Sand			550	600			
Slate & Shell			600	800			
Salt Sand			800	910			
Slate & Shell			910	1340			
Maxon Sand			1340	1400			
Slate & Shells			1400	1445			
Little Lime			1445	1470			
Slate & Shell			1470	1510			
Big Lime			1510	1660			
Injun Sand			1660	1700			
Slate Shells			1700	1743			
Oil Sand			1743	1768			
Total Depth				1768			



MAY 27 1938

