





STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

968

Permit No. 412-A

Oil or Gas Well 011  
(KIND)

WELL RECORD


Company Virginian Gasoline & Oil Company  
Address P. O. Box 2633, Charleston, W. Va.  
Farm Edward Gebhart Acres 900  
Location (waters) Blue Creek  
Well No. 3188 Elev. 1214.7  
District Elk County Kanawha  
The surface of tract is owned in fee by \_\_\_\_\_  
Address \_\_\_\_\_  
Mineral rights are owned by Kanawha Crude Oil Co.  
Address Charleston, W. Va.  
Drilling commenced June 5, 1915  
Drilling completed August 10, 1915  
Date Shot 8-17-15 From 2248 To \_\_\_\_\_  
With 20 Qts.  
Open Flow /10ths Water in \_\_\_\_\_ Inch  
/10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
Oil 20 bbls., 1st 24 hrs.  
Fresh water \_\_\_\_\_ feet  
Salt water 1235 feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
18			Size of
10			
8 1/4	902	902	Depth set
6 1/2	1855	1855	
5 3/16	2183	Pulled	Perf. top
3			Perf. bottom
2			Perf. top
Liners Used			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_

COAL WAS ENCOUNTERED AT 295 FEET 24 INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand				50			
Red Rock			50	75			
Slate			75	200			
Sand			200	290			
Slate			290	295			
Coal			295	297			
Slate			297	398			
Lime			398	450			
Little Dunkard			450	500			
Slate			500	600			
Big Dunderd			600	725			
Lime Shells			725	1025			
Black Slate			1025	1145			
Salt Sand			1145	1665	Water	1235	
White Slate			1665	1670			
Red Rock			1670	1715			
Lime			1715	1750			
Red Rock			1750	1755			
Sand			1755	1765			
Lime			1765	1770			
Maxon Sand			1770	1790			
Slate			1790	1800			
Little Lime			1800	1847			
Pencil Cave			1847	1855			
Big Lime			1855	2015	Gas	1950	
Red Lime			2015	2050	Gas	2080	
Squaw Sand			2050	2110			
Lime			2110	2125			
Blue Creek Sand			2125	2150	Gas	2150	
Weir Sand			2150	2268	Oil & Gas	2258	Green
Total Depth				2271	More Oil	2250	



(Over)

MAR 30 1944

