



STATE OF WEST VIRGINIA
DEPARTMENT OF MINES
OIL AND GAS DIVISION

1753

WELL RECORD

Permit No. KAN-929-A

Oil or Gas Well Oil
(KIND)

Company The Pure Oil Company
Address P. O. Box 591, Newark, Ohio
Farm Williams Coal Co. Acres 12,000
Location (waters) _____
Well No. 116 Elev. 967'
District Cabin Creek County Kanawha
The surface of tract is owned in fee by Shank Land Company
and Kanawha Banking & Trust Co. Inc.
Address Charleston, W. Va.
Mineral rights are owned by Same as above
Address _____
Drilling commenced July 14, 1917
Drilling completed September 10, 1917
Date Shot 9-19-17 From 2654' To 2666'
With 40 lbs. Nitroglycerine


Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10 3/4"	360'	360'	Size of
8 1/4"	1335'	Pulled	
6 3/8"	2003'	2003'	Depth set
5 3/16"			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

Open Flow /10ths Water in _____ Inch
/10ths Merc. in _____ Inch
Volume _____ Cu. Ft.
Rock Pressure _____ lbs. _____ hrs.
Oil 11 bbls. Pumped bbls., 1st 24 hrs.
Fresh water 325' feet feet
Salt water _____ feet feet

CASING CEMENTED _____ SIZE _____ No. Ft. _____ Date _____

COAL WAS ENCOUNTERED AT 250 FEET 60 INCHES
325 FEET 36 INCHES 345 FEET 60 INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES
_____ FEET _____ INCHES _____ FEET _____ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Clay	Yellow		0	15			
Line	white		15	90			
Slate	black		90	105			
Shells	white		105	165			
Sand	white		165	190			
Slate	black		190	250			
Coal	black		250	255			
Line	white		255	300			
Sand	yellow		300	325			
Coal	black		325	328	water	325'	24 blrs per hr.
Sand	gray		328	345			
Coal	Black		345	350			
Sand	gray		350	400			
Slate	black		400	415			
Shells	white		415	475			
Slate	black		475	575			
Sand	white		575	680			
Slate & Shells	white		680	785			
Sand	white		785	880			
SHANGHAI Line	Yellow		880	980			
Slate & Shells	white		980	1035			
SALT SAND	white		1035	1335			
Slate	black		1335	1400			
Line	white		1400	1420			
Slate	black		1420	1500			
Line	white		1500	1570			
Rock	red		1570	1600			
Slate	white		1600	1650			
Rock	red		1650	1725			
Line, shells	white		1725	1878			
Little Line	black		1878	1968			
Pencil slate	Black		1968	1978			
BIG LINE	white		1978	2210			
IRON SAND	red		2210	2240			
Shells	white		2240	2275			
Line	black		2275	2320			
Slate & Shells	white		2320	2616			
Shale	brown		2616	2626			
IRON SAND	white		2626	2666	Oil	2656'-2666'	
Slate	black		2666	2667			



TOTAL DEPTH

(Over) 2667'
DEC 10 1952

