





STATE OF WEST VIRGINIA  
DEPARTMENT OF MINES  
OIL AND GAS DIVISION

1784

WELL RECORD

Oil or Gas Well Oil  
(KIND)



Permit No. 1017-A

Company PRESTON OIL CO.  
Address P. O. Box 1273 Charleston 25, W. Va.  
Farm C. A. Stover Acres 2.47  
Location (waters) Cabin Creek  
Well No. 1 - F-2444 Elev. 697'  
District Cabin Creek County Kanawha  
The surface of tract is owned in fee by \_\_\_\_\_  
Address \_\_\_\_\_  
Mineral rights are owned by C. A. Stover  
Address \_\_\_\_\_  
Drilling commenced \_\_\_\_\_  
Drilling completed 10-25-16  
Date Shot \_\_\_\_\_ From \_\_\_\_\_ To \_\_\_\_\_  
With \_\_\_\_\_  
Open Flow \_\_\_\_\_ /10ths Water in \_\_\_\_\_ Inch  
\_\_\_\_\_ /10ths Merc. in \_\_\_\_\_ Inch  
Volume \_\_\_\_\_ Cu. Ft.  
Rock Pressure \_\_\_\_\_ lbs. \_\_\_\_\_ hrs.  
Oil \_\_\_\_\_ bbls., 1st 24 hrs.  
Fresh water \_\_\_\_\_ feet \_\_\_\_\_ feet  
Salt water \_\_\_\_\_ feet \_\_\_\_\_ feet

Casing and Tubing	Used in Drilling	Left in Well	Packers
Size			Kind of Packer
16			
13			
10			Size of
8 1/2			
6 5/8	<u>1738'</u>	<u>1738'</u>	Depth set
5 3/16			
3			Perf. top
2			Perf. bottom
Liners Used			Perf. top
			Perf. bottom

CASING CEMENTED \_\_\_\_\_ SIZE \_\_\_\_\_ No. Ft. \_\_\_\_\_ Date \_\_\_\_\_  
COAL WAS ENCOUNTERED AT 190 FEET 36 INCHES  
397 FEET 36 INCHES 497 FEET 36 INCHES  
\_\_\_\_\_ FEET \_\_\_\_\_ INCHES \_\_\_\_\_ FEET \_\_\_\_\_ INCHES

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Sand & Gravel			0	15			
Lime			15	25			
Gravel			25	35	Hole full water		
Sand			35	110			
Slate			110	140			
Sand			140	190	Hole full water		
Coal			190	193			
Slate			193	230			
Lime			230	305			
Sand			305	345			
lime			345	370			
Slate			370	397			
Coal			397	400			
Slate			400	425			
Sand			425	465			
Slate			465	497			
Coal			497	500	5 Bailers Water		
Sand			500	530			
Lime			530	610			
Grampus			610	760	H. F. Water 650'		
Lime			760	770			
Slate			770	773			
Salt Sand			773	1065			
Slate			1065	1070			
Lime			1070	1125			
Slate & Shells			1125	1210			
Red Rock			1210	1245			
Slate			1245	1540			
Maxon Sand			1540	1600			
Little Lime			1600	1635			
Pencil Cave			1635	1645			
Lime			1645	1670			
Slate			1670	1701			
Big Lime			1701	1906	Show gas 1830'		
Big Injun, Red			1906	1940			
Slate			1940	1960			
Sand			1960	1980			
Slate & Shells			1980	2110			
Lime			2110	2150			



(Over) JAN 2 1954  
JAN 2 RECD

Formation	Color	Hard or Soft	Top	Bottom	Oil, Gas or Water	Depth Found	Remarks
Slate & Shells			2150	2310			
Lime			2310	2330			
Slate			2330	2355			
Lime			2355	2360			
Coffee Slate			2360	2368			
Berea Grit			2368	2406			
Lime			2406	2412			
Total depth			2412'				

NOT RECORDED

Date September 1, 19 53

APPROVED THE PRESTON OIL COMPANY, Owner

By S. R. Ferrell  
(Title)  
Manager Civil Engineering Department