

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: TOLLE, CHESTER L Operator Well No.: 1

LOCATION: Elevation: 1442' Quadrangle: FAIRMONT EAST 7.5'  
District: UNION County: MARION  
Latitude: 8219' Feet South of 39 Deg. 27 Min. 30 Sec.  
Longitude: 10559' Feet West of 80 Deg. 02 Min. 30 Sec.

Well Type: OIL ☒ GAS ☒

Company UNKNOWN - WVDEP PAID PLUGGING CONTRACT Coal Operator \_\_\_\_\_  
601 57TH STREET or Owner \_\_\_\_\_  
CHARLESTON, WV 25304 \_\_\_\_\_  
Agent H. JASON HARMON Coal Operator \_\_\_\_\_  
Permit Issued Date 03-19-2025 or Owner \_\_\_\_\_

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of LEWIS ss:

JAMES CLAYTON ("CLAY") COCHRAN and KEVIN PAUL QUESENBERRY being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 26TH day of MARCH, 2025, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
TAG TD	1108'			
PULL TBG	1108'	197'	2" TBG (911')	197'
COULD NOT PULL CSG	SURFACE	742'	5 3/16" CSG (NONE)	742'
BH PLUG CEMENT	1108'	607'	PUMP CLASS A CEMENT (36 SACKS)	
GEL SPACER	607'	395'		
PERF 4 HOLES	235'	110'		
SURFACE PLUG CEMENT	395'	SURFACE	PUMP CLASS A CEMENT (120 SACKS)	

Description of monument: ONE JOINT PIPE; 36" ABOVE; 10' BELOW; TO STATE SPECS and that the work of plugging and filling said well was completed on the 2ND day of APRIL, 2025.


And further deponents saith not.

Sworn and subscribe before me this 8TH day of APRIL, 2025

My commission expires: OCTOBER 10, 2029

Notary Public

Affidavit reviewed by the Office of Oil and Gas: Ky Willett Title: Inspector



04/18/2025





04/18/2025