

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: Jesse Stewart Operator Well No.: 3712

LOCATION: Elevation: 1183' Quadrangle: Mannington WV 7.5'  
District: Mannington County: Marion  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 33 Min. 45.59 Sec.  
Longitude: \_\_\_\_\_ Feet West of 80 Deg. 21 Min. 33.78 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co Coal Operator 1 Bridge St  
or Owner Monongah, WV 26554  
Coal Operator \_\_\_\_\_  
Agent Ronnie Harsh Coal Operator \_\_\_\_\_  
or Owner \_\_\_\_\_  
Permit Issued Date 07/14/2017

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of Marion ss:


Michael P. Mitchell and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 25th day of August, 2017, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Expandable	1265'	1076'		
Thixotropic	1076'	746'		
Expandable	746'	Surface		
8 5/8"	882'	1265'	501'	383'
10 3/4"	30'	366'	0'	326'
16" Conductor	Surface	10'	0'	10'

Description of monument: 7" of 7" casing with company name, well #, API #, and date cemented  
said well was completed on the 20th day of September, 2017.

and that the work of plugging and filling

And further deponents saith not. Michael P. Mitchell  
Kevin S. Wright



Sworn and subscribe before me this 30th day of Oct, 2017

My commission expires: 9-15-22  
Carol A Mayle  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: Shel Dukes III Title: COG Inspector

RECEIVED  
Office of Oil and Gas

NOV 01 2017  
11/10/2017  
WV Department of  
Environmental Protection

FORM WR-38  
(Affidavit of Plugging)

WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address

MARY J. HIBBS  
Lease or Property Owner  
62 Brooklyn Ln Mannington, WV 26582  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address

MANNINGTON WV 7.5'  
Well Location  
MANNINGTON  
District

MARION  
County

3712  
Well No.

JESSE STEWART  
Farm

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

MICHAEL P. MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 26<sup>th</sup> day of August, 2017 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Drilled out cement and gel plugs inside 10 3/4" casing from 30' to 356'. Drilled out cement and gel plugs out of 8 5/8" casing from 381' to 1265'. Tagged cement plug at 1265'. Pulled 8 5/8" casing from 381' to 858' with extreme difficulty. Pilot milled 8 5/8" casing from 858' to 882'. Attempted to pull remaining 8 5/8" casing by pulling over 150% of string weight. Attempt was unsuccessful. Left 383' of 8 5/8" casing in well from 882' to 1265'. Cut remaining 8 5/8" casing at 1080' and 977'. Cleaned out well with 9 7/8" bit from surface to 882'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam (869.5 - 876'). Attempted to remove 10 3/4" casing by pulling over 150% of string weight. Attempt was unsuccessful. Left 326' of 10 3/4" casing in well from 30' to 356'. <b>Cemented hole from 1265' back to Surface as follows:</b> From 1265' to 1076' with 45 sacks of Expandable cement. From 1076' to 746' with 130 sacks of Thixotropic cement with green dye. From 746' to the surface with 280 sacks of Expandable cement. Cement did circulate at the surface. Left 10' of 16" conductor casing in well from surface to 10'.	8 5/8"	501'	383'	
		10 3/4"	0'	326'
		16" Conductor	0'	10'
Coal Seams		Description of Monument		
Pittsburgh	(870' - 876')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 20th day of September, 2017

And further deponents saith not.

Michael P. Mitchell  
Michael P. Mitchell

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 30 day of Oct 2017

Carol A. Mayle  
Notary Public

My commission expires: 9-15-22



Permit No. 47-049-00332-P  
Well No. 3712  
Latitude: 39° 33' 45.59"N  
Longitude: 80° 21' 33.78"W

RECEIVED  
Office of Oil and Gas

NOV 1 2017

WV Department of  
Environmental Protection  
11/10/2017