

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5057
Well No.
BAKER, JOHN #2
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]* 5-5-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

BRETT HOWELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 20th day of March, 2014 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from the surface to 165'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 165' to 720'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 671' to 678'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 720' to 878'. <u>Cemented hole from 878' to the surface as follows:</u> From 878' to 566' with 115 sacks of Thixotropic Cement with Green Dye. From 566' to surface with 230 sacks of Expandable Cement. Cement did circulate at the surface. Left 17' of 16" conductor casing in the hole from the surface to 17'.		16" Conductor	0'	18'
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	671' to 678'	77" of 7" casing w/company name, well number,		
(Name)		permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
(Name)		cement plug at ground level.		

RECEIVED
Office of Oil & Gas
MAY 06 2014
WV Department of
Environmental Protection

... And that the work of plugging and filling said well was completed on the 2nd day of April, 2014.

And further deponents saith not.

Brett Howell
Brett Howell


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 5th day of May 2014

Kara Beth Ford
Notary Public

My commission expires: 11/14/23

Permit No. 47-49-00642-P
Well No. 5057



05/09/2014