

STATE OF WEST VIRGINIA
DEPARTMENT OF ENVIRONMENTAL PROTECTION
OFFICE OF OIL AND GAS

DATE: February 15th, 2016
API #: 47-049-00775P
Lease No:

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm Name: EDDY, JAMES E. Operator Well No.: 563 DEPI (CNGD 563)
Plugging (2015)

LOCATION: Elevation: 1378.76' Quadrangle: Fairmont West
District: Union County: Marion
Latitude: 000 Feet South of: 39 Deg. 27 Min. 30 Sec.
Longitude: 10,425 Feet West of: 80 Deg. 07 Min. 30 Sec.

Well Type: OIL GAS X

Company: CNX Gas Company LLC Coal Operator or Owner See List on Page 2
P.O. Box 1248
Jane Lew, WV 26378

Agent: Matthew Imrich
Permit Issued Date: 11/21/2014

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of Lewis ss:

Richard C. Jones and Anthony Kendziora being first duly sworn according to law do depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 17th day of June, 2015, and the well was plugged and filled in the following manner:

Received
FEB 18 2016
Office of Oil and Gas
Environmental Protection
WV Dept.

| TYPE | FROM | TO | PIPE REMOVED | LEFT |
|---------------------|-------|---------|-----------------------|--------------------|
| Class A Cement Plug | 3121' | 2975' | 3046' (1 1/2" tubing) | |
| 6% Gel Plug | 2975' | 2470' | | |
| Class A Cement Plug | 2470' | 2240' | 1000' (4 1/2" csg) | 2174' (4 1/2" csg) |
| 6% Gel Plug | 2240' | 1550' | | |
| Class A Cement Plug | 1550' | 1150' | | 1257' (8 5/8" csg) |
| 6% Gel Plug | 1150' | 1000' | | |
| Class A Cement Plug | 1000' | 770' | | |
| 6% Gel Plug | 770' | 215' | | |
| Class A Cement Plug | 215' | Surface | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |

Description of monument: Installed 6" x 14' monument with API # 47-049-00775.


and that the work of plugging and filling said well was completed on the 17th day of June, 2015.

NOTE:

And further deponents saith not. Richard C. Jones

Sworn and subscribe before me this 29th day of January

My commission expires: Sept. 26, 2021



Notary Public

Affidavit reviewed by the Office of Oil and Gas Beth Henderson Title: Environmental Inspector