

FORM WR-38
(Affidavit of Plugging)STATE OF WEST VIRGINIA
DEPARTMENT OF ENERGY
OIL AND GAS WELLS DIVISION

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.

Coal Operator or Owner

P. O. BOX 100, OSAGE, WV 26543

Address

CONSOLIDATION COAL CO.

Coal Operator or Owner

1800 WASHINGTON RD., PITTSBURGH, PA 15241

Address

STEPHEN F. & ROBERTA JEAN SMITH

Lease or Property Owner

1208 AVALON ST., MORGANTOWN WV, 26505

Address

CONSOLIDATION COAL CO.

Name of Well Operator

P.O. BOX 100 OSAGE, WV 26543

Complete Address

12-24

97

WELL LOCATION

MANMINGTON

District

MARION

County

6121

WELL NO.

STEPHAN F. SMITH & ROBERTA JEAN SMITH

FARM

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of HARRISON

Ss:

G. ANDREW LANG

and

KEVIN WRIGHT

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by CONSOLIDATION COAL COMPANY well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9TH day of 12-96 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Plugs Used	Casing Pulled	Casing Left In
Formation		Size & Kind		
CLEANED HOLE WITH 9 7/8" BIT TO 1081', TOP OF 8" CASING. LEFT 8" CASING IN HOLE FROM 1081' TO 1424'. CLEANED 7 7/8" HOLE FROM 1081' TO 1530'. CLEANED 9 7/8" HOLE THRU PITTSBURGH COAL FROM 943' TO 951'. RAN COAL PROTECTION STRING AS FOLLOWS: 246.03' OF 2 3/8" TUBING FOLLOWED BY 1244.08' OF 4 1/2" CASING. CEMENTED HOLE FROM 1500.11' BACK TO SURFACE USING 590 SACKS OF POZ MIX AND 235 SACKS OF THIXATROPIC CEMENT. CEMENT DID CIRCULATE. USED 1000 GALLONS OF MUD FLUSH. LATCH DOWN PLUG AT 1117.16'. FLOAT VALVE AT 1244.08'. SWEDGE AT 1245.08'. DISPLACED CEMENT TO 1117.16' WITH WATER LET SET AND BAILED DRY.		8 5/8"	0	1424'
TOTAL DEPTH: 1,530 FEET				
Coal Seams		Description of Monument		
(Name) PITTSBURGH	943' TO 951'	5' OF 4 1/2" CASING WITH		
(Name)		PLAQUE STATING CONSOLIDATION		
(Name)		COAL CO. WELL 6121		
(Name)		PERMIT # 47-49-1059-P		

and that the work of plugging and filling said well was completed on the 18TH day of December 1996

And further deponents STATING not.


Sworn to and subscribed before me this

24TH

day of

12-96

08/28/2026

My commission expires:
06-29-99

Notary Public