

*Rec'd 4/21/02
w/ S. Messers Rel.*

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

<u>Consolidation Coal Co. (17/21 Interest)</u> Coal Operator or Owner	<u>Consolidation Coal Co.</u> Name of Well Operator
<u>P.O. Box 100 Osage, WV. 26543</u> Address	<u>P.O. Box 100 Osage, WV. 26543</u> Complete Address
<u>Consolidation Coal Co.</u> Coal Operator or Owner	<u>August 20</u> 19 <u>98</u> WELL AND LOCATION
<u>PO. Box 100 Osage, WV. 26543</u> Address	<u>Mannington</u> District
<u>Marciline Huey (4/21 Interest)</u> Lease or Property Owner	<u>Marion</u> County
<u>306 Highland Ave., Mannington, WV. 26582</u> Address	WELL NO. <u>R-417</u>
	<u>Macilne Huey</u> Farm

STATE INSPECTOR SUPERVISING PLUGGING

AFFIDAVIT

*DEP O&G website word
4372410, 27 } kw
54880, 8253 } 11/7/2007*

STATE OF WEST VIRGINIA,
County of Monongalia

ss:

Larry L. Yost and Dennis L. Yost

being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Co., well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 10th day of July, 1998, and that the well was plugged and filled in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing	
			CSG PULLED	CSG LEFT IN
	Pulled 2800' of cable;	Cable	2800'	
	Pulled 2800' of 2 3/8" tubing; Pulled 2775' of 5 1/2" casing. Cleaned wellbore to 2785'. Cemented bottom hole plug from 2785' - 1672' with 250 sacks of cement. Pulled 1255' of 7" casing. Made cuts in 7" at 1670'. Ran coal protection string as follows; 1006' of 4 1/2" casing; 636' of 2 3/8" tubing Latch down plug at 986'; Float valve at 1006'; Swedge at 1006'.	2 3/8" 5 1/2" 7"	2800' 2775' 1255'	
	175 sacks of expanding type cement; 250 of mud flush.	TOP-1255'		
Coal Seams		Description of Monument		
(Name) Pittsburgh -842'		6 ft. of 4 1/2" casing with plaque stating Consol		
(Name) 852'	Let set, bailed dry, set monument.	R-417.47-49-01088-P		
(Name)				
(Name)				

and that the work of plugging and filling said well was completed on the 29th day of July, 19 98.


And further deponents saith not.

*Larry L. Yost
Dennis L. Yost*

Sworn to and subscribed before me this 20th day of August, 19 98.

Charles Skinner
Notary Public

My commission expires
March 12, 2002



Permit No. 47-49-01088-P

SEP 27 2002

MAR 10 8 8 P