

STATE OF WEST VIRGINIA  
DEPARTMENT OF ENVIRONMENTAL PROTECTION  
OFFICE OF OIL AND GAS

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE IN TRIPLICATE, one copy mailed to the Department, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

Farm name: J.L. Dulaney Operator Well No.: 4285

LOCATION: Elevation: 1243.92' Quadrangle: Mannington W.VA  
District: Mannington County: Marion  
Latitude: \_\_\_\_\_ Feet South of 39 Deg. 36 Min. 59.59 Sec.  
Longitude: \_\_\_\_\_ Feet West of -80 Deg. 21 Min. 56.00 Sec.

Well Type: OIL \_\_\_\_\_ GAS X

Company Consolidation Coal Co. Coal Operator Consolidation Coal Co.  
1 Bridge Street or Owner 1 Bridge Street  
Monongah, WV 26554 Monongah, WV 26554  
Agent David Roddy Coal Operator \_\_\_\_\_  
Permit Issued Date 0824/2021 or Owner \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of Monongalia ss:

Matthew A. Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by the above named well operator, and participated in the work of plugging and filling the above well say that said work was commenced on the 6th day of January, 2022, and the well was plugged and filled in the following manner:

TYPE	FROM	TO	PIPE REMOVED	LEFT
Throtropic w/ Green Dye and Gas Block	1277'	854'		
Expandable Cement	854'	Surface		
8 5/8" Casing	1138'	Unknown	0' (cut at 1162')	Unknown
16" Conductor	Surface	20'	0'	20'

Description of monument: 77" of 7" casing with company name, well #, API #, and date cemented and that the work of plugging and filling said well was completed on the 25 day of January, 2022.

And further deponents saith not. Matthew A. Yearsley  
Kevin S. Wright



Sworn and subscribe before me this 18th day of Feb, 2022

My commission expires: 09/15/22  
[Signature]  
Notary Public

Affidavit reviewed by the Office of Oil and Gas: \_\_\_\_\_ Title: \_\_\_\_\_

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE STREET MONONGAH, WV 26554  
Address  
ANNETTE M SPEERHAS  
Lease or Property Owner  
293 PLEASANTVIEW DR. MIDLAND, PA 15059  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE STREET MONONGAH, WV 26554  
Complete Address  
MANNINGTON W.VA  
Well Location  
MANNINGTON  
District  
MARION  
County  
4285  
Well No.  
J.L. DULANEY  
Farm

STATE INSPECTOR SUPERVISING PLUGGING \_\_\_\_\_

AFFIDAVIT


STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

Matthew Yearsley and Kevin S. Wright being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 6<sup>th</sup> day of January, 2022 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
	Cleaned a 12 1/4" hole from the surface to 207'. Reduced the hole to 9 7/8" at 207'. Cleaned a 9 7/8" hole from 207' to 1138'. Tagged the top of the existing 8 5/8" casing at 1138'. Reduced the hole to 7 7/8" at 1138'. Cleaned a 7 7/8" hole from 1138' to 1277'. Attempted to remove the existing 8 5/8" casing by pulling 150% of the string weight but all attempts were unsuccessful. Left an unknown amount of 8 5/8" casing in the hole from 1138' to an unknown depth. Cut remaining 8 5/8" casing at 1162'. Cleaned a 9 7/8" hole through the Pittsburgh Coal Seam (1054.2' to 1061.5'). Left 20' of 16" conductor in the hole from the surface to 20'.	8 5/8" Casing 16" Conductor	0' 0'	Unknown 20'
	<b><u>Cemented the hole from 1277' back to the surface as follows:</u></b> From 1277' to 854' with 185 sacks of Thixotropic Cement with Green Dye and a Gas Blocker additive. Tagged the top of Thixotropic cement plug at 854'. From 854' to the surface with 445 sacks of Expandable Cement. Cement did circulate at surface. A total of 630 sacks of cement were used to fill the hole from 1277' to the surface.			
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>Pittsburgh</u>	1154.2' – 1061.5'	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 25<sup>th</sup> day of January, 2022

And further deponents saith not.



Matthew A. Yearsley  
Matthew A. Yearsley

Kevin S. Wright  
Kevin S. Wright

Sworn to and subscribed before me this 19<sup>th</sup> day of Feb, 2022

[Signature]  
Notary Public

My commission expires: 09/15/22

Permit No. 47-049-01113  
Well No. 4285  
Latitude: 39° 36' 59.59"N  
Longitude: -80° 21' 56.00"W