

ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
CONSOLIDATION COAL CO.  
Coal Operator or Owner  
1 BRIDGE ST. MONONGAH WV 26554  
Address  
CONSOLIDATION COAL CO.  
Lease or Property Owner  
1 BRIDGE ST. MONONGAH, WV 26554  
Address

CONSOLIDATION COAL CO.  
Name of Well Operator  
1 BRIDGE ST. MONONGAH, WV 26554  
Complete Address  
GLOVER GAP 7.5'  
Well Location  
MANNINGTON  
District  
MARION  
County  
8004  
Well No.  
CONSOLIDATION COAL CO.  
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Bill Heskett 5-5-14*

AFFIDAVIT

STATE OF WEST VIRGINIA,  
County of MONONGALIA ss:

**RUSSELL SMALLWOOD** and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 27<sup>th</sup> day of February, 2014 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 3 1/2" hole from the surface to 3039'. Perforated 4 1/2" casing with 6 shots in 30" at the following depths: 2500', 2400', 2300', 2200', 2100', 2000', 1900', 1800', 1700', 1600', 1500' and 1400'. 4 1/2" casing was previously perforated at the following depths: 2995', 2975', 2905', 2880', 2795', 2735', 2705' and 2605'. Cemented bottom hole plug from 3039' to 1375' with 100 sacks of Expandable Cement with Gas Blocker additive. Removed 1373' of 4 1/2" casing from the surface to 1373'. Left 1681' of 4 1/2" casing in the hole from 1373' to 3054'. Cut 7" casing at the following depths: 903', 803', 596', 496', 396', 296', 196' and 96'. Removed 88' of 7" casing from 8' to 96' with extreme difficulty due to cement bond. Sand cut 7" and 9 5/8" casing at the following depths: 708', 706', 704', 702', 700', 698', 696', 694', 692', 690', 688' and 686'. Sand cut 7" and 9 5/8" casing through the Pittsburgh Coal seam from 695' to 703'. Left approximately 1664' to 7" casing in the hole from 96' to 1760'. Left approximately 725' of 9 5/8" casing in the hole from the surface to 725'. Left 19' of 13 3/8" casing in the hole from the surface to 19'. All casing depths taken from previous well record.	16" Conductor	0'	12'	
		13 3/8" Casing	0'	19'
		9 5/8" Casing	0'	725'
		7" Casing	88'	1664'
		4 1/2" Casing	1373'	1681'
<b>Cemented hole from top of bottom hole plug at 1375' back to surface as follows:</b> From 1375' to 913' with 60 sacks of Expandable Cement. From 913' to 595' with 55 sacks of Thixotropic Cement with Dye. From 595' to surface with 110 sacks of Expandable Cement. Cement did circulate at the surface. Left 12' of 16" conductor casing in the hole from the surface to 12'.				
<b>Coal Seams</b>		<b>Description of Monument</b>		
<u>PITTSBURGH</u>	695' to 703'	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

RECEIVED  
Office of Oil & Gas  
MAY 06 2014  
WV Department of  
Environmental Protection

... And that the work of plugging and filling said well was completed on the 19<sup>th</sup> day of March, 2014.

And further deponents saith not.


*Russell Smallwood*  
Russell Smallwood

*Kevin S. Wright*  
Kevin S. Wright

Sworn to and subscribed before me this 1st day of April 2014

*Kara Beth Ford*  
Notary Public

My commission expires: 11/4/23



05/09/2014