

COPY

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address
SPORTSMANS SQUARE CIRCLE
Lease or Property Owner
129 CIRCLE DR. FAIRMONT, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26582
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5077
Well No.
SPORTSMANS SQUARE CIRCLE
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William Handrich*

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of June, 2011 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Plugs Used Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from surface to 352'. Cleaned 9 7/8" hole from 352' to 777' top of 7" casing. Cleaned 6 1/4" hole from 777' to 1689'. Drilled Cement from 776' to 1007'. Run cement bond log on 7" casing. Log indicated that the 7" casing was cemented in hole from 809' to 1250'. Removed 7" casing from 771' to 809' with extreme difficulty. Section milled 7" casing from 930' to 960'. Cut remaining casing at 1682', 1582', 1482', 1382', 1289', 1149', 1100', 1050', 988' 878', 835', and 813'. Section milled 7" casing thru Pittsburgh Coal 941' to 949'. Left 20' of 16" casing in hole from 20' to surface. Cement hole from 1689' back to surface as follows. From 1689' to 1149' with 71 sacks of 35/65 Poz mix. From 1149' to 841' with 55 sacks of Thixotropic Cement with green dye. From 841' with 289 sacks of Econofill Cement. A total of 424 sacks of Cement. Cement did circulate at surface.	16" Conductor 7" Casing	0' 38"	20' 884'	
Coal Seams		Description of Monument		
<u>PITTSBURGH</u>	<u>941' to 949'</u>	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.		
(Name)				
(Name)				
(Name)				

... and that the work of plugging and filling said well was completed on the 11th day of July, 2011

And further deponents saith not.



Sworn to and subscribed before me this

15th day of October, 2011

My commission expires:

March 18, 2020

Mike Mitchell
Mike Mitchell

Kevin S. Wright
Kevin S. Wright
10/21/2011

Jacqueline L. Shriver
Notary Public

Permit No. 47-49-02169-P
Well No. 5077