

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JEFFERY MICHAEL & RONALD C. MICHAEL
Lease or Property Owner
P.O. Box 211 Mannington WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

GLOVER GAP 7.5'
Well Location

MANNINGTON
District

MARION
County

5244
Well No.

MICHAEL, JEFFREY & RONALD
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...* 4-20-12

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 16th day of January, 2012 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned 12 1/4" hole from the surface to 242'. Removed 394' of 7" casing from 242' to 636'. Continued to clean 12 1/4" hole from 242' to 421'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 421' to top of 7" casing at 1085'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1085' to 1986'. Tagged plug at 1986'. Removed 191' of 7" casing from 1085' to 1276'. Left 660' of 7" casing in the hole from 1276' to 1936'. Cut remaining 7" casing at the following depths; 1865', 1770', 1685', 1616', 1545', 1456' and 1364'. Cleaned 9 7/8" hole from 1085' to 1276'. Cleaned 9 7/8" hole through the Pittsburgh Coal (937'- 944'). Left 20' of 16" conductor pipe in the hole from 20' to surface.	16" Conductor 7" Casing	0' 585'	20' 660'
	Cemented hole from 1986' back to surface as follows: From 1986' to 1144' with 145 sacks of Super Lite Cement. From 1144' to 837' with 138 sacks of SuperTropic Cement with white dye. From 837' to surface with 505 sacks of Super Lite Cement. A total of 788 sacks of cement were used to fill the hole from 1986' back to surface. Cement did circulate at the surface.			
Coal Seams		Description of Monument		
Pittsburgh	(937' - 944')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 3rd day of February, 2012

And further deponents saith not.


Delbert Moore
Delbert Moore

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 16th day of April, 2012

Jacqueline S. Shriver
Notary Public

My commission expires:
March 18, 2020



Permit No. 47-049-02198-P
Well No. 5244