

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
TOMMY L. SNODGRASS
Lease or Property Owner
RR 1 BOX 258 MOUNDSVILLE, WV 26041
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5256
Well No.
SNODGRASS, TOMMY L.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...* 3-6-13

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and **KEVIN WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 24th day of January, 2013 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from the surface to 149'. Removed junk debris from hole with 11 1/4" float basket from 149' to 160'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 160' to 1177'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1177' to 1178'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1178' to 1192'. Tagged solid plug at 1192'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 741' to 747'. Left 20' of 16" conductor casing in the hole from the surface to 20'. Cemented hole from 1192' back to surface as follows: From 1192' to 947' with 115 sacks of SuperLite Cement. From 947' to 641' with 170 sacks of Super Tropic Cement with white dye. From 641' to surface with 330 sacks of SuperLite Cement. A total of 615 sacks of cement were used to fill the hole from 1192' back to surface. Cement did circulate at the surface.	16" Conductor	0'	20'	
Coal Seams		Description of Monument		
Pittsburgh	(741' - 747')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil & Gas
MAR 06 2013
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 6th day of February, 2013


And further deponents saith not.

Delbert Moore
Delbert Moore
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 28th day of Feb 2013

Carol A. Mayle
Notary Public

My commission expires: 9-12-2017



Permit No. 47-049-02205-P
Well No. 5256

03/08/2013