

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5334
Well No.
CONSOLIDATION COAL CO.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]* 7-13-12

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of May, 2012 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
	Cleaned 12 1/2" hole from the surface to 255'. Reduced hole to 9 7/8" at 255'. Cleaned 9 7/8" hole from 255' to 1026'. Reduced hole to 7 7/8" at 1026'. Cleaned 7 7/8" hole from 1026' to 1101'. Tagged plug at 1101'. Cleaned 9 7/8" hole through Pittsburgh Coal (801' - 806'). Left 20' of 16" conductor pipe in the hole from 20' to surface. Cemented hole from 1101' back to surface as follows: From 1101' to 701' with 170 sacks of SuperTropic Cement with white dye. From 701' to surface with 280 sacks of Super Lite Cement. A total of 450 sacks of cement were used to fill the hole from 1101' back to surface. Cement did circulate at the surface.	16" Conductor	0'	20'
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	(801' - 806')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil & Gas
JUL 18 2012
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 11th day of June, 2012


And further deponents saith not.

[Signature]
Delbert Moore
[Signature]
Kevin S. Wright

Sworn to and subscribed before me this 9th day of July 2012

[Signature]
Notary Public

My commission expires:
March 18, 2020



Permit No. 47-049-02208-P
Well No. 5334

07/20/2012