

AFFIDAVIT OF PLUGGING AND FILLING WELL

ORIGINAL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CHARLES P. GLOVER
Lease or Property Owner
2598 BUFFALO BRINK ROAD MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

GLOVER GAP 7.5'
Well Location
MANNINGTON
District

MARION
County

5335
Well No.

GLOVER, CHARLES P.
Farm

STATE INSPECTOR SUPERVISING PLUGGING [Signature]

AFFIDAVIT


STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of February, 2013 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Removed 602' of 2 3/8" tubing from the hole from the surface to 602'. Cleaned 12 1/2" hole from the surface to 222'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 222 to 778'. Fished 2 3/8" junk from hole from 602' to 652'. Drilled cement and 2 3/8" tubing from 652' to 778'. Reduced hole to 6 1/2". Drill cement and 2 3/8" tubing from 778' to 838'. Clean 6 1/2" hole from 838' to 1119'. Tag solid plug at 1119'. Cleaned 6 1/2" hole through the Pittsburgh Coal seam from 803' to 809'. Possible 2 3/8" tubing reaming in coals seam. Left 20' of 16" conductor casing in the hole from the surface to 20'.		16" Conductor	0'	20'
RECEIVED Office of Oil & Gas JUN 24 2013 WV Department of Environmental Protection				
Coal Seams		Description of Monument		
Pittsburgh	(803' - 809')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 2nd day of April, 2013

And further deponents saith not.



Sworn to and subscribed before me this 3rd day of June

[Signature]
Delbert Moore

[Signature]
Kevin S. Wright

[Signature]
Notary Public

My commission expires: Feb. 16, 2021

Permit No. 47-049-02240-P
Well No. 5335

07/19/2013