

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

JEFFREY MICHAEL
Lease or Property Owner
P.O BOX 211 MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address

GLOVER GAP 7.5'
Well Location

MANNINGTON
District

MARION
County

5130
Well No.

MICHAEL JEFFERY
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. ...* 3-6-13

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

ROBERT STEEL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 21st day of December, 2012 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/2" hole from the surface to 292'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 292' to the top of the 8 5/8" casing at 944'. Removed 12' of 8 5/8" casing from 944' to 956'. Pilot milled 8 5/8" casing from 856' to 969'. Removed 277' of 8 5/8" casing with extreme difficulty due to casing being ripped. Left 166' of 8 5/8" casing in the hole from 1246' to 1412'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1022' to 1030'. Clean 7 7/8" hole from 1246' to the top of the 7" casing at 1455'. Left unknown amount of 7" casing in the hole from 1455' to unknown depth. Cleaned 6 1/4" hole from 1455' to 1564'. 20' of 16" conductor casing left in the hole from the surface to 20'.	16" Conductor	0'	20'	
		8 5/8" Casing	302'	166'
		7" Casing	0'	unknown
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>(1022' - 1030')</u>	<u>77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

RECEIVED
Office of Oil & Gas
MAR 06 2013
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 17th day of January, 2013

And further deponents saith not.

Robert Steel
Robert Steel


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 12th day of February, 2013

Jaqueline J. Shriver
Notary Public

My commission expires:

March 18, 2020



Permit No. 47-049-02244-P
Well No. 5130

03/08/2013