

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5114
Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING *William H. Henscheid* 3-6-13

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of January, 2013 and that the well was plugged in the following manner:

Sand or Zone Record	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Formation				
Cleaned 12 1/4" hole from the surface to 213'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 213' to 1302'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1302' to 1393'. Reduced hole to 6 1/4". Tagged solid plug at 1393'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1044' to 1052'. Left 20' of 16" conductor casing in the hole from the surface to 20'. <u>Cemented hole from 1393' back to surface as follows:</u> From 1393' to 1252' with 60 sacks of 35/65 Poz Mix Cement. From 1252' to 944' with 150 sacks of Thixotropic Cement with White Dye. From 944' to surface with 311 sacks of Econofill Cement. Cement did circulate at the surface.	16" Conductor	0'	20'	
Coal Seams		Description of Monument		
Pittsburgh	(1044' - 1052')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil & Gas
MAR 06 2013
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 1st day of February, 2013


And further deponents saith not.

Mike Mitchell
Mike Mitchell
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 26th day of Feb 2013

Carol A. Mearls
Notary Public

My commission expires: 9-12-2017



03/08/2013