

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26582
Address

CONSOLIDATION COAL COMPANY
Lease or Property Owner
1 BRIDGE STREET, MONONGAH 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26582
Complete Address
CLOVER GAP 7.6'
Well Location
MANNINGTON
District
MARION
County
5017
Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING

William H. ... 5-30-13

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE MITCHELL and KEVIN S. WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 19th day of March, 2013 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
	Cleaned 12 1/2" hole from the surface to 263'. Reduced hole to 9 7/8". Clean 9 7/8" hole from 263' to 1194'. Removed 7" junk casing at 897'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1194' to 1197'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 765' to 773'. Possible junk metal may remain in the coal seam. Left 15' of 16" conductor casing in the hole from the surface to 15'. <u>Cemented hole from 1197' back to surface as follows:</u> From 1197' to 973' with 100 sacks of Superlite Cement. From 973' to 665' with 145 sacks of Thixotropic Cement w/ dye. From 665' to surface with 340 sacks pf Superlite Cement. A total of 440 sacks of Superlite Cement and 145 sacks of Thixotropic Cement was used to cement the hole from 1197' to surface. Cement did circulate at the surface.	16" Conductor	0'	15'
<u>Coal Seams</u>		RECEIVED Office of Oil & Gas MAY 30 2013 WV Department of Environmental Protection		
<u>PITTSBURGH</u>	765' to 773'	Description of Monument		
(Name)		77" of 7" casing w/company name, well number,		
(Name)		permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
		cement plug at ground level.		

... And that the work of plugging and filling said well was completed on the 3rd day of April, 2013

And further deponents saith not.


Mike Mitchell
Mike Mitchell

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 29th day of April 2013

Carole A. Mayle
Notary Public

My commission expires: 9-12-2017



Permit No. 47-49-02253-P
Well No. 5017

05/31/2013