

ORIGINAL

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
MATHEW M CALL
Lease or Property Owner
1688 DENTS RUN ROAD MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
CLOVER GAP 7.6'
Well Location
MANNINGTON
District
MARION
County
5163
Well No.
CALL, MATHEW M.
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of **MONONGALIA** ss:

MIKE MITCHELL and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 23rd day of April, 2013 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from the surface to 260'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 260' to 1324'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1324' to 1354'. Tagged solid plug at 1354'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 867' to 873'. Left 16' of 16" conductor casing in the hole from the surface to 16'. Cemented hole from 1354' back to surface as follows: From 1354' to 1073' with 120 sacks of 35/65 Poz Mix Cement. From 1073' to 767' with 135 sacks of Thixotropic Cement w/ dye. From 767' to surface with 280 sacks of Econofill Cement. A total of 535 sacks of cement was used to cement the hole from 1354' to surface. Cement did circulate at the surface.	16" Conductor	0'	16'	
Coal Seams		Description of Monument		
PITTSBURGH	867' to 873'	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7"		
(Name)		casing. Well marker will be attached to the		
(Name)		cement plug at ground level.		

RECEIVED
Office of Oil & Gas
JUN 24 2013
WV Department of
Environmental Protection

... And that the work of plugging and filling said well was completed on the 7th day of May, 2013

And further deponents saith not.

Mike Mitchell
Mike Mitchell


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 3rd day of June 2013

Carol A. Mayle
Notary Public

My commission expires: 9-12-2017

Permit No. 47-49-02256-P
Well No. 5163



07/19/2013