

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE ST. MONONGAH WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE ST. MONONGAH, WV 26554
Address


CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE ST. MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5014
Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING *Delbert Moore* 3-17-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

DELBERT MOORE and **KEVIN S. WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of January, 2014 and that the well was plugged in the following manner:

Formation	Filling Material	Casing Size & Kind	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from surface to 303'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 303' to 624'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 624' to 2045'. Tagged solid plug at 2045'. Removed 148' of 7" casing from 624' to 772' with extreme difficulty due to casing being bonded and ripped. Left unknown amount of 7" casing in the hole from 772' to an unknown depth. Cut remaining 7" casing at the following depths: 2043', 1943', 1843', 1743', 1643', 1543', 1443', 1343', 1243', 1143', 1046', 940', and 832'. Cut 7" casing through the Pittsburgh Coal seam from 780' to 786.5' at the following depths: 790', 788', 786', 784', 782', 780', 778', 776', and 774'.		16" Conductor 7" Casing	0'	20' Unknown
Cemented hole from 2045' back to surface as follows: From 2045' to 987' with 310 sacks of Expandable Cement. From 987' to 680' with 115 sacks of Thixotropic Cement with green dye. From 680' to surface with 190 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams	Description of Monument			
<u>PITTSBURGH</u>	780' to 786.5'			
(Name)	77" of 7" casing w/company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to the cement plug at ground level.			
(Name)				

... And that the work of plugging and filling said well was completed on the 5th day of February, 2014.

And further deponents saith not.

Delbert Moore
Delbert Moore


Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 10th day of March 2014

Kara Beth Forst
Notary Public

My commission expires: November 4, 2023

Permit No. 47-49-02275-P
Well No. 5014



03/28/2014