

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
WILLIS E. & PATTY R. ANDERSON
Lease or Property Owner
403 LONG DRAIN ROAD MANNINGTON, WV 26582
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5546
Well No.
BEATTY, J.L.
Farm

STATE INSPECTOR SUPERVISING PLUGGING Bill Flacher 5-12-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

... MIKE CAMPBELL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 3rd day of April, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from the surface to 251'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 251' to 778'. Tagged top of 8 5/8" casing at 778'. Removed 259' of 8 5/8" casing from 778' to 1037'. Continued to clean 9 7/8" hole from 778' to 1037'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1037' to 1422'. Tagged solid plug at 1422'. Left 156' of 8 5/8" casing in the hole from 1037' to 1193'. Cut remaining 8 5/8" casing at the following depth: 1102'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 789' to 796'. <u>Cemented hole from 1422' back to surface as follows:</u> From 1422' to 996' with 360 sacks of Expandable Cement. From 996' to 689' with 155 sacks of Thixotropic Cement with Dye. From 689' to the Surface with 80 sacks of Expandable Cement. A total of 595 sacks of cement were used to fill the hole from 1422' back to surface. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.	16" Conductor	0'	20'	
Coal Seams		Description of Monument		
Pittsburgh	(789' - 796')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil & Gas
MAY 19 2014
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 24th day of April, 2014


And further deponents saith not.

Mike Campbell
Mike Campbell
Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 9th day of May 2014

Kara Beth Forst
Notary Public

... My commission expires: 11/4/23



Permit No. 47-049-02289-P
Well No. 5546

05/23/2014