

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
PRISCILLA HAMILTON
Lease or Property Owner
3 BEHLAR ROAD, FAIRVIEW, WV 26570
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5338
Well No.
HAMILTON, PRISCILLA
Farm

STATE INSPECTOR SUPERVISING PLUGGING *[Signature]*

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

MIKE CAMPBELL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 28th day of April, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from the surface to 308'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 308' to 1057'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1057' to 1554'. Tagged solid plug at 1554'. Cleaned 9 7/8" hole through the Pittsburgh Coal Seam from 982' to 988'. Removed 160' of 8 5/8" casing from 1057' to 1217'. Left 238' of 8 5/8" casing in the hole from 1217' to 1454'. Cut remaining 8 5/8" casing at the following depth: 1303'.		16" Conductor	0'	20'
<u>Cemented hole from 1554' back to surface as follows:</u> From 1554' to 1188' with 80 sacks of Expandable Cement. From 1188' to 882' with 160 sacks of Thixotropic Cement with Green Dye. From 882' to the Surface with 400 sacks of Expandable Cement. A total of 640 sacks of cement were used to fill the hole from 1554' back to surface. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams		Description of Monument		
Pittsburgh	(982' - 988')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

RECEIVED
Office of Oil and Gas
JUN 23 2014
WV Department of
Environmental Protection

... and that the work of plugging and filling said well was completed on the 9th day of May, 2014


And further deponents saith not.

[Signature]
Mike Campbell
[Signature]
Kevin S. Wright

Sworn to and subscribed before me this 5th day of June 2014

[Signature]
Kara Beth Forst
Notary Public

My commission expires:
November 4, 2023



Permit No. 47-049-02298-P
Well No. 5338

06/27/2017