

49-02311P

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5126
Well No.
CONSOLIDATION COAL COMPANY
Farm

STATE INSPECTOR SUPERVISING PLUGGING Beth Handberg 10-2-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

ROGER MOORE and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 9th day of July, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 276'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 276' to 760'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 760' to 1715'. Cleaned 7 7/8" hole through the Pittsburgh Coal seam from 786' to 793'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1715' to 2438'. Left 268' of 8 5/8" casing in the hole from 1054' to 1322'. Remaining 8 5/8" casing was cut at the following depths: 1216' and 1126'. Cemented bottom hole with 325 sacks of Expandable Cement. Tagged top of bottom hole plug at 1000'.		16" Conductor	0'	20'
		8 5/8"	0'	268'
<u>Cemented hole from 1000' back to surface as follows:</u> From 1000' to 652' with 170 sacks of Thixotropic Cement with green dye. From 652' back to the Surface with 410 sacks of Expandable Cement. Cement did circulate at the Surface. Left 20' of 16" conductor casing in the hole from Surface to 20'.		Received Office of Oil & Gas OCT 02 2014		
Coal Seams		Description of Monument		
Pittsburgh	(786' - 793')	77' of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.		

... and that the work of plugging and filling said well was completed on the 25th day of July, 2014

And further deponents saith not.


Roger Moore
Roger Moore

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 8th day of September 2014

Kara Beth Forst
Notary Public

My commission expires: 11/4/23



Permit No. 47-049-02311-P
Well No. 5126

10/10/2014