

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL CO.
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5127
Well No.
CONSOLIDATION COAL COMPA
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Brett Howarth

10-2-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

BRETT HOWELL and KEVIN WRIGHT being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 18th day of July, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/2" hole from Surface to 138'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 138' to 1185'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 750' to 757'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 1185' to 1195'. Reduced hole to 6 1/2". Cleaned 6 1/2" hole from 1195' to 1201'. Tagged solid plug at 1201'. <u>Cemented hole from 1201' back to surface as follows:</u> From 1201' to 982' with 90 sacks of Expandable Cement. From 982' to 636' with 195 sacks of Thixotropic Cement with green dye. From 636' back to the Surface with 300 sacks of Expandable Cement. Cement did circulate at the Surface. Left 20' of 16" conductor casing in the hole from Surface to 20'.	16" Conductor	0'	20'	
Coal Seams	Description of Monument			
Pittsburgh (750' - 757')	77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.			

Received
Office of Oil & Gas
OCT 02 2014

... and that the work of plugging and filling said well was completed on the 30th day of July, 2014

And further deponents saith not.


Brett Howell
Brett Howell

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 9th day of September 2014

Kara Beth Forst
Notary Public

My commission expires 11/23



Permit No. 47-049-02313-P
Well No. 5127