

AFFIDAVIT OF PLUGGING AND FILLING WELL

AFFIDAVIT SHOULD BE MADE IN TRIPLICATE, one copy mailed to the Division, one copy to be retained by the Well Operator and the third copy (and extra copies if required) should be mailed to each coal operator at their respective addresses.

CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL COMPANY
Coal Operator or Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address
CONSOLIDATION COAL COMPANY
Lease or Property Owner
1 BRIDGE STREET MONONGAH, WV 26554
Address

CONSOLIDATION COAL CO.
Name of Well Operator
1 BRIDGE STREET MONONGAH, WV 26554
Complete Address
GLOVER GAP 7.5'
Well Location
MANNINGTON
District
MARION
County
5108
Well No.
CONSOLIDATION COAL COMPA
Farm

STATE INSPECTOR SUPERVISING PLUGGING

Bill Henscheid

10-2-14

AFFIDAVIT

STATE OF WEST VIRGINIA,
County of MONONGALIA ss:

RUSSELL SMALLWOOD and **KEVIN WRIGHT** being first duly sworn according to law depose and say that they are experienced in the work of plugging and filling oil and gas wells and were employed by Consolidation Coal Company well operator, and participated in the work of plugging and filling the above well, that said work was commenced on the 31st day of July, 2014 and that the well was plugged in the following manner:

Sand or Zone Record Formation	Filling Material	Casing/Tubing Size	Casing Pulled	Casing Left In
Cleaned 12 1/4" hole from Surface to 232'. Reduced hole to 9 7/8". Cleaned 9 7/8" hole from 232' to 951'. Tagged top of 8 5/8" casing at 951'. Reduced hole to 7 7/8". Cleaned 7 7/8" hole from 651' to 1674'. Reduced hole to 6 1/4". Cleaned 6 1/4" hole from 1674' to 1684'. Tagged solid plug at 1684'. Removed 374' of 8 5/8" casing from 951' to 1325'. Cleaned 9 7/8" hole through the Pittsburgh Coal seam from 1101' to 1108'. Left 260' of 8 5/8" casing in the hole from 1325' to 1585'.		16" Conductor 8 5/8" Casing	0' 374"	20' 260'
<p>Received Office of Oil & Gas OCT 02 2014</p>				
<u>Cemented hole from 1684' back to surface as follows:</u> From 1684' to 1308' with 90 sacks of Expandable Cement. From 1308' to 1001' with 130 sacks of Thixotropic Cement with green dye. From 1001' back to the Surface with 390 sacks of Expandable Cement. Cement did circulate at the surface. Left 20' of 16" conductor casing in the hole from the surface to 20'.				
Coal Seams		Description of Monument		
<u>Pittsburgh</u>	<u>(1101' - 1108')</u>	<u>77" of 7" casing w/ company name, well number, permit number and date cemented stated on 7" casing. Well marker will be attached to cement plug at ground level.</u>		

... and that the work of plugging and filling said well was completed on the 15th day of August, 2014

And further deponents saith not.


Russell Smallwood
Russell Smallwood

Kevin S. Wright
Kevin S. Wright

Sworn to and subscribed before me this 12 day of September 2014

Kara Beth Forst
Notary Public

My commission expires: 11/1/23



Permit No. 47-049-02318-P
Well No. 5108

10/10/2014